

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
Finley State Office Building  
130 South Market, Rm 2078  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-175-21414 - 0000

LEASE NAME MORGAN "I"

WELL NUMBER 2

2970 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 8 TWP. 32 RGE. 33 (E) or (W)

COUNTY SEWARD

Date Well Completed 4-08-95

Plugging Commenced 12-14-95

Plugging Completed 12-18-95

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS P.O. BOX 351, LIBERAL, KS 67901-0351

PHONE # ( 316 ) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well DRY

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12-13-95 (date)

by DEWAYNE RANKIN AND GARY WINTER (KCC District Agent's Name).

Is ACO-1 filed? YES If not, is well log attached? \_\_\_\_\_

Producing Formation NONE Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 5800

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8", 24#	1542	NONE
				5-1/2", 15.5#	5838	2700'

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.  
MIRU CASING PULLERS. PMP 2 SX HULLS & 25 SX CMT, DISP W/MUD TO 4169-3969. PULL FREE POINT & SHOOT OFF 5-1/2" CSG AT 2700. PULL CSG TO 2500 & SPOT 25 SX CMT FROM 2500-2400. PULL TO 1570 & SPOT 50 SX FROM 1570-1470. PULL TO 700 & SPOT 40 SX FROM 700-600. PULL TO 40 & SPOT 10 SX FROM 40-0. CUT OFF CASING 3' BELOW GL AND CAP. PERMANENTLY INSCRIBE WELL NAME, LOCATION AND DATE PLUGGED ON CAP. KCC WITNESS REPS DEWAYNE RANKIN AND GARY WINTERS.  
STATE CORPORATION COMMISSION

(If additional description is necessary, use BACK of this form.)

JAN 04 1996

Name of Plugging Contractor SARGENT & HORTON PLUGGERS License No. 31151

Address RT. 1, BOX 49A, TYRONE OKLAHOMA 73951-9731

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF KANSAS COUNTY OF SEWARD, ss.

DAVID W. KAPPLE (Employee of Operator) or (xxxxxxx) of above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) David Kapple

(Address) P.O. BOX 351, LIBERAL, KS 67901-0351

SUBSCRIBED AND SWORN TO before me this 29th day of December, 19 95

My Commission Expires: \_\_\_\_\_



Freda L. Hinz  
Notary Public