

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-175-10054-0000

LEASE NAME Ks. Univ. GU

WELL NUMBER D #2

SPOT LOCATION N W/4

SEC. 9 TWP. 32 RGE. 33 ~~EX~~ or (W)

COUNTY Seward

Date Well Completed 5-63

Plugging Commenced 2-13-1988

Plugging Completed 2-18-88

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Amoco Production Company

ADDRESS Box 432, Liberal, Ks. 67901

PHONE # (316) 624-6241 OPERATORS LICENSE NO. 5952

Character of Well Gas
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? yes If not, is well log attached? _____

Producing formation Chase Depth to top 2582 bottom 2634 T.D. 2690'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface				8 5/8"	620'	0'
Production	(Chase) Gas	2582	2634	4 1/2"	2689'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state the character of same and depth placed, from feet to feet each set. Well had sand 1730' to TD

Ran 2 3/8" tubing to 1660' & pump 40 sks. cement
Lay down tubing to 900' & pump 50 sks. cement - cement circulated
Lay down tubing & fill hole with 10 sks. cement.
Cut off 3' below ground level & cap

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Midwest Casing Pulling Service License No. 6497
Address Box F, Sublette, Ks. 67877

STATE OF KANSAS COUNTY OF HASKELL, ss.

I, Edgar J. Eves ~~(employee of operator)~~ or
(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filled, that the same are true and correct, so help me God.

(Signature) Edgar J. Eves
(Address) Box F

2-25-88
CONC. DIVISION
SUBSCRIBED AND SWORN TO before me this 19th day of Feb., 1988

Sondra L. Eves
Notary Public

My Commission expires: 12-6-88

