


15-175-20219-0000

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Seward County, Sec. 28 Twp. 32S Rge. (E) 33 (W)

Location as "NE/CNW*SW*" or footage from lines C S/2 SE/4
Lease Owner Gulf Oil Corporation
Lease Name Lemert Well No. 3
Office Address P. O. Box 12116, Oklahoma City, OK 73112
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed 6-19 19 74
Application for plugging filed 6-19 19 74
Application for plugging approved 6-19 19 74
Plugging commenced 6-19 19 74
Plugging completed 6-20 19 74
Reason for abandonment of well or producing formation Dry hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production - 19-
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eddie Eves
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 6071 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Heebner			4080	16"	40'	0
Toronto	no shows		4096	8-5/8"	1529'	0
Lansing	"		4213			
Marmaton	"		4850			
Cherokee	"		5055			
Morrow	"		5414			
Chester	"		5604			
St. Genevieve	"		5804			
St. Louis	"		5884			

RECEIVED
STATE CORPORATION COMMISSION
JUL 3 1974
CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

- 9# mud 6071 to 1400'
- 8-5/8 CIBP 1400'
- 9# mud 1400 to 1012'
- 45 sx cmt. plug 1012 to 895'
- 9# mud 895 to 50'
- 20 sx cmt. plug 50 to 5' Cut 8-5/8" csg. off at 5 ft. & welded 1/4" plate on 8-5/8"
- Surface soil 5' to 0'

RECEIVED
STATE CORPORATION COMMISSION
JUN 26 1974
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Service Drilling Company
Address P. O. Box 910, Borger, Texas 79007

STATE OF Oklahoma COUNTY OF Oklahoma, ss.
J. D. Horne (employee of owner) ~~owner or operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. D. Horne
P. O. Box 12116, Oklahoma City, OK 73112
(Address)

SUBSCRIBED AND SWORN TO before me this 2 day of July, 1974

My commission expires 1-9-78
J. P. Wagner Notary Public.

15-175-20219-0000

Lemert No. 3
Sec. 28-32S-33W
Seward County, Kansas

RB & sd.	0 - 580
RB & anhyd.	580 - 1530
lm.	1530 - 1900
lm. & sh.	1900 - 2750
Sh.	2750 - 3095
lm & sh	3095 - 3817
sh	3817 - 4275
sh & lm	4275 - 6071

RECEIVED
STATE CORPORATION COMMISSION

JUN 28 1974

CONSERVATION DIVISION
Wichita, Kansas