

3-11

RECEIVED
KANSAS CORPORATION COMMISSION

2-

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

APR 01 1994

CONSERVATION DIVISION
WICHITA, KS

API NUMBER: 15-173-20,877-0000
N2 NE SW, SECTION 23 TOWNSHIP 29 RANGE 3W

OPERATOR LICENSE # 30129 2285 FEET FROM S SECTION LINE
3410 FEET FROM E SECTION LINE

OPERATOR EAGLE CREEK CORPORATION
NAME & 107 N MARKET #509
ADDRESS WICHITA KS 67202

LEASE NAME: LEMON TRUST #2-23A
COUNTY: SEDGWICK
WELL TOTAL DEPTH: 4165' 135.36

PIPE: 5-1/2" @ 3835'
SURFACE CASING: 8-5/8" @ 726'

ABANDONED OIL WELL GAS WELL INPUT WELL SMD D&A

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: VAL ENERGY INC
ADDRESS: P O BOX 322, HAYSVILLE KS 67060 LICENSE: 5822

COMPANY TO PLUG AT: HOUR: 10:00 DAY: 11 MONTH: 3 YR: 1994

PLUGGING PROPOSAL RECEIVED FROM: DISTRICT 2

COMPANY NAME: UNITED CMT PHONE: 316-321-4680

WERE: SAND BACK & SPOT 5 SX CMT @ 3620' - SHOOT 5-1/2" CSG @ 2657' - PULL CSG TO 780' & SPOT 35 SX - PULL CSG TO 350' & SPOT 25 SX - PULL CSG TO 60' & SPOT 25 SX

PLUGGING PROPOSAL RECEIVED BY: TODD ALLAM

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()

COMPLETED: HOUR: 17:00 DAY: 11 MONTH: 3 YEAR: 1994

ACTUAL PLUGGING REPORT:
SANDED BACK & SPOTTED 5 SX CMT @ 3620' - SHOT 5-1/2" CSG @ 2657' - DUE TO WRONG PRE-TALLY, SET NEXT 2 SPOTS IN WRONG PLACES - RAN CSG TO 780' & SPOTTED 35 SX CMT - PULLED CSG TO 350' & SPOTTED 25 SX CMT - PULLED CSG TO 60' & SPOTTED 25 SX CMT

REMARKS: UNITED #4850 & #4851 - 150 SX CMT - 60/40 POZ 4% GEL

INVOICED
DID OBSERVE THIS PLUGGING.

DATE APR 01 1994
INV. NO. 40209

/s/ JERRY CLARK (AGENT)