

1 120889

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

2-8

API NUMBER 15-189-21,600-0000
SW SE SE, SEC. 12, T 31 S, R 35
330 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5363
Operator: BEREXCO INC.
Name & Address: 100 N. Broadway, Ste. 970
Wichita, KS 67202-2209

Lease Name M.L. Long Well # 1-12
County Stevens 186.88
Well Total Depth 5750 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1728

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ O&A _____ X
Other well as hereinafter indicated _____

Plugging Contractor BEREDCO INC. License Number 5147
Address 401 E. Douglas, Wichita, KS 67202

Company to plug at: Hour: 2 a.m. Day: 8 Month: 2 Year: 19 94

Plugging proposal received from Kent
(company name) BEREDCO INC. (phone) 316-265-2856

work: to fill hole with heavy mud and spot cement through drill pipe
1st plug at base of Hugoton/Council Grove with 100 sx cement,
2nd plug at 1750' with 50 sx cement, 3rd plug at 600' with 50 sx cement,
4th plug at 40' with 10 sx cement, 5th plug to circulate rathole with 15 sx cement,
6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None _____ X

Operations Completed: Hour: 5:30 a.m. Day: 8 Month: 2 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug at 3150' with 100 sx cement,
2nd plug at 1750' with 50 sx cement,
3rd plug at 600' with 50 sx cement,
4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement,
6th plug to circulate mousehole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

FEB 10 1994

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE FEB 11 1994

INV. NO. 39912

Signed Duane Rankin (TECHNICIAN)

2-8 APR 09 1994

KCC USE: EFFECTIVE DATE: 1-29-94
 DISTRICT # 1
 SGA? Yes No

State of Kansas
 NOTICE OF INTENTION TO DRILL 189-21,600

FORM C-17/91
 FORM MUST BE SIGNED
 ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date January 27, 1994
 month day year
 OPERATOR: License # 5363
 Name: BEREXCO INC.
 Address: 100 North Broadway, Suite 970
 City/State/Zip: Wichita, Kansas 67202-2209
 Contact Person: Evan Mayhew
 Phone: 316.265.3311
 CONTRACTOR: License #: 5147
 Name: BEREDCO INC

Spot SW - SE - SE Sec 12 Twp 31 S, Rg 35 East XX West
330 feet from South/North Line of Section
900 feet from East/West line of Section
 IS SECTION XX REGULAR IRREGULAR?
 (NOTE: Locate well on the Section Plat or Reverse Side)
 County: STEVENS
 Lease Name: M.L. LONG Well #: 1-12
 Field Name: CUTLER, SE, EXT
 Is this a Prorated/Spaced Field? yes XX no
 Target Formation(s) MORROW
 Nearest Lease or unit boundary: 330
 Ground Surface Elevation: EST. 2955 feet MSL
 Water well within one-quarter mile: yes XX no
 Public water supply well within one mile: yes XX no
 Depth to bottom of fresh water: 450
 Depth to bottom of usable water: 500
 Surface Pipe by Alternate: XX 1 2
 Length of Surface Pipe Planned to be set: (1475) 520
 Length of Conductor pipe required: NA
 Projected Total Depth: 520
 Formation at Total Depth: MORROW
 Water Source for Drilling Operations: well farm pond XX other
 DWR Permit #: APPLIED FOR
 Will Cores Be Taken?: yes XX no
 If yes, proposed zone:

Well Drilled For: Well Class: Type Equipment:
 XX Oil ___ Enh Rec ___ Infiled ___ XX Mud Rotary
 XX Gas ___ Storage ___ XX Pool Ext. ___ Air Rotary
 OWWO ___ Disposal ___ Wildcat ___ Cable
 Seismic; # of Holes ___ Other ___
 Other: _____
 OWWO: old well information as follows:
 Operator: _____
 Well Name: _____
 Comp. Date: _____ Old Total Depth _____
 Directional, Deviated or Horizontal wellbore? yes ___ XX no
 yes, true vertical depth: _____
 Bottom Hole Location

Prorated miss (chester) (C-8430) 520' Alt. I Req.
 Exp. 7/24/94 AFFIDAVIT

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-

at seq. It is agreed that the following minimum requirements will be met:

1. Notify the appropriate district office prior to spudding of well;
2. A copy of the approved notice of intent to drill shall be posted on each drilling rig;
3. The minimum amount of surface pipe as specified below shall be set by circulating cement to the top' in all cases surface pipe shall be set through all unconsolidated materials plus a minimum of 20 feet into the underlying formation;
4. If the well is dry hole, and agreement between the operator and the district office on plug length and placement is necessary prior to plugging;
5. The appropriate district office will be notified before well is either plugged or production casing is cemented in;
6. IF AN ALTERNATE II COMPLETION, PRODUCTION PIPE SHALL BE CEMENTED FROM BELOW ANY USABLE WATER TO SURFACE WITHIN 120 DAYS OF SPUD DATE. IN ALL CASES, NOTIFY DISTRICT OFFICE PRIOR TO ANY CEMENTING

RECEIVED
 STATE CORPORATION COMMISSION
 FEB 10 1994
 CONSERVATION DIVISION
 Wichita, Kansas

Pusher Kauf
 SPUD DATE 1-29-94 INIT. SM
 LENGTH SURFACE PLANNED 1728
 RESERVE PIT STATUS- REMOVE FLUID LINED
 after salt sect. bbls. when done bbls.
 RATHOLED AHEAD? Y ___ N ___ SIZE HOLE ___
 SURFACE PIPE 8 3/4 @ 1728 CONDUCTOR
 ANHYDRITE T- B- ELEVATION
5200 steel dug
 TD 5250 FORMATION
 RAN PIPE @ ___ DV TOOL ___ ALT II DONE ___
 SX ___ Y ___ N ___
 ___ Arbuckle Plug @ ___ Ft. W/ ___ SX
 ___ Hug./Council @ 3150 local Ft. W/ 180 SX
 ___ Anhydrite Base @ 1750 Ft. W/ 50 SX
 ___ 1/2 Base Anyh. @ 1600 Ft. W/ 50 SX
 ___ 1/2, 1/2 Plug @ 600 Ft. W/ 50 SX
 ___ Bottom Surface @ ___ Ft. W/ ___ SX
 ___ 40' Plug @ 410 Ft. W/ 10 SX
 RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ 10 SX
 WATER WELL ___ SX (Irr. Well ___ Pond ___)
 Hauling ___
 TECHNICIAN DR DATE 2-4-94
 TYPE OF CEMENT 60-40-670
 STARTING TIME 2:00 (AM/PM) DATE 2-8-94
 COMPLETION TIME 5:30 (AM/PM) DATE 2-8-94
 CEMENT COMPANY Halliburton