

To: 1 020662 4-20
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 9/61 15-189-10027-0000

SW NE, SEC. 12, T 31 S, R 35 W/E
3300 feet from S section line
1940 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5208
Operator: Mobil Oil Corporation
Name & Address 2319 N. Kansas
Liberal, KS 67901

Lease Name G.B. Strong Well # 1-A
County Stevens 187.52
Well Total Depth 5770 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 655

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated Dual completion 1961-68, Water injection well 1968-78,
Abandoned since 1978
Plugging Contractor Sargent & Horton Plugging, Inc. License Number 31151
Address Rt. 1, Box 49BA, Tyrone, OK 73951-9731

Company to plug at: Hour: 1 p.m. Day: 19 Month: 4 Year: 19⁹³

Plugging proposal received from Don Horton
(company name) Sargent & Horton Plugging, Inc. (phone) 405-854-6515

Work: 5 1/2" at 5769' w/550 sx cement, PBTD 5730', Perfs at 5345-54, 5562-68, 5578-85'
DV @ 3005', Could not release packer or get down tubing past 1909'. Pulled 1900' of tubing.
1st plug run good string of tubing to 1760', pump 40 sx cement,
2nd plug pull tubing to 700' and pump 30 sx cement,
3rd plug pull tubing to one joint and fill to surface with 10 sx cement.

Plugging Proposal Received by Glenn Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4 p.m. Day: 20 Month: 4 Year: 19⁹³

ACTUAL PLUGGING REPORT 1st plug ran good tubing string to 1760', pumped 40 sx cement,
2nd plug pulled tubing to 700' and pumped 30 sx cement,
3rd plug pulled tubing to one joint and filled to surface with 10 sx cement.

DV tool @ 3005 cemented to surface w/ 700sx

Remarks: Used common cement by Sargent & Horton. No casing recovery. Pulled 1900' of tubing.
(If additional description is necessary, use BACK of this form)

Observe this plugging.

DATE 5-4-93

INV. NO. 37649
4-20

Signed Glenn R. Barlow
(TECHNICIAN)

STATE CORPORATION COMMISSION
RECEIVED
APR 28 1993
CONSERVATION DIVISION
Wichita, Kansas