

020781

7-19

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 189-21,486 - 0000  
C SE NW, SEC. 11, T 7 S, R 31 35    
3300 feet from S section line  
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License / 5003

Lease Name Lambert "A" Well / 1-11

Operator: McCoy Petroleum Corporation

County Stevens

Name: 3017 N. Cypress

Well Total Depth 5900 191.75 feet

Address Wichita, KS 67226-4003

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 1796

Abandoned Oil Well  Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor J.W. Gibson Well Service License Number 5866

Address 7400 E. Orchard Rd., Ste. 370, Englewood, CO 80111

Company to plug at: Hour: 8:30 a.m. Day: 19 Month: 7 Year: 19 94

Plugging proposal received from Tom Patton

(company name) J.W. Gibson Well Service (phone) 405-338-0664

Logs: 5 1/2" at 5898' w/400 sx cement, PBD 5789', Perfs at 5442-48, 5651-55'

1st plug set CIBP at 5390' with 2 sx cement on top,

2nd plug spot 50 sx cement at 1815',

3rd plug spot 40 sx cement at 600',

4th plug spot 10 sx cement at 40'.

Plugging Proposal Received by Steve Middleton  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part  None \_\_\_\_\_

Operations Completed: Hour: 5:15 p.m. Day: 19 Month: 7 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug set CIBP at 5390' and dumped 2 sx cement on top,

2nd plug spotted 50 sx cement at 1830',

3rd plug spotted 40 sx cement at 630',

4th plug spotted 10 sx cement at 40 to -4'.

Gel mud between all plugs.

Remarks: Used common cement by J.W. Gibson. Recovered 1839' of 5 1/2" casing.  
(if additional description is necessary, use BACK of this form.)

**INVOICED**  
Observe this plugging.

DATE 7-26-94

Signed Glen R. Barlow  
(TECHNICIAN)

INV. NO. 40884

7-19

Rec'd 7-25-94