

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-10058-00-00
Spot: CNW Sec/Twnshp/Rge: 2-32S-33W
1320 feet from N Section Line, 1370 feet from W Section Line
Lease/Unit Name: LOUIS S. LEMERT Well Number: 2
County: SEWARD Total Vertical Depth: 2775 feet

Operator License No.: 5952 1119
Operator Name: AMOCO PRODUCTION COMPANY Conductor Pipe: Size _____ feet:
Address: 2225 WEST OKLAHOMA AVENUE Surface Casing: Size 8.625 feet: 607 WITH 650 SX CMT
ULYSSES, KS 67880 Production: Size 4.5 feet: 2756 WITH 1000 SX CMT
Liner: Size _____ feet: _____ 90.19

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/09/2000 11:30 AM
Plug Co. License No.: 5287 Plug Co. Name: HALLIBURTON SERVICES
Proposal Rcvd. from: JOE EUDEY Company: AMOCO Phone: (316) 356-6981

Proposed Plugging Method: PUMP 4 SX HULLS & HOLE FULL OF CMT. 50 SX FOR BACKSIDE.

Plugging Proposal Received By: SCOTT ALBERG WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 11/09/2000 12:50 PM KCC Agent: KEVIN STRUBE

Actual Plugging Report:

PERFS AT 2724-26, 2712-14, 2670-80, 2706-20'. PUMPED DOWN 4 1/2" CASING 300# HULLS & 150 SX CMT. MAXIMUM PRESSURE 200#. HOLE STAYED LOADED. PUMPED DOWN 8 5/8 X 4 1/2 ANNULUS 17 SX CMT. CMT STAYED AT SURFACE. MAXIMUM PRESSURE 300#.

RECEIVED
STATE CORPORATION COMMISSION
NOV 20 2000
CONSERVATION DIVISION
Wichita, Kansas

Remarks: USED 65/35 POZMIX 6% GEL BY HALLIBURTON. NO CASING RECOVERED.

Plugged through: CSG

District: 01

Signed

Kevin D Strube

(TECHNICIAN)

INVOICED

DATE

11/21/00

WV. NO.

2001061002

NOV 15 2000

Form CP-243