

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-175-20765-00-00  
Spot: CSWNW Sec/Twnshp/Rge: 2-32S-33W  
1980 feet from N Section Line, 660 feet from W Section Line  
Lease/Unit Name: L S LEMERT A Well Number: 1  
County: SEWARD Total Vertical Depth: 6000 feet

Operator License No.: 5952  
Op Name: AMOCO PRODUCTION COMPANY  
Address: 2225 WEST OKLAHOMA AVENUE  
ULYSSES, KS 67880

Conductor Pipe: Size 20 feet: 40  
Surface Casing: Size 9.625 feet: 1667 WITH 775 SX CMT  
Production: Size 7 feet: 6000 WITH 360 SX CMT  
Liner: Size feet: \$195.00

Well Type: OIL UIC Docket No: Date/Time to Plug: 09/19/2001 11:00 AM  
Plug Co. License No.: 5287 Plug Co. Name: HALLIBURTON SERVICES  
Proposal Rcvd. from: SPANKY Company: BP AMOCO Phone: (316) 356-6955

Proposed Plugging Method: CIBP @ 4140'. 1ST PLUG CIBP @ 1850. PERFORATE AT 1750'. PUMP CMT FROM 1750-0'.

Plugging Proposal Received By: STEVE DURRANT Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 09/19/2001 2:30 PM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

PBTD 5985'. PERFS AT 4250-51'. CIBP @ 4140' WITH 2 SX CMT ON TOP. PERFORATE CASING AT 3400'. HALLIBURTON PUMPED 100 SX CMT 65/35 6% 3% CC. SET CIBP @ 1850'. PERFORATE CASING AT 1750'. PUMP 345 SX CMT FROM 1750' TO 0'. FILL INSIDE 7" AND BACKSIDE OF 7". STAYED FULL.

Remarks: USED 65/35 POZMIX 65 GEL BY HALLIBURTON. NO CASING RECOVERED.

Plugged through: CSG

District: 01

Signed:  (TECHNICIAN)

RECEIVED

SEP 24 2001

KCC WICHITA

INVOICED

DATE 9-24-01

INV NO 2002060589

SEP 20 2001

Form 