

To: 1020833 12-22
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
20th COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 175-21,334-0000

SE SE NE, SEC. 29, T 32 S, R 32 W/E
2970 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9262

Lease Name Kane Well # 1

Operator: Lowry Exploration, Inc.

County Seward

Name & Address P.O. Drawer 1847

Well Total Depth 6040 19630 feet

Liberal, KS 67905-1847

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1698

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Sargent's Casing Pulling Inc. License Number 6547

Address P.O. Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 10:30 a.m. Day: 21 Month: 12 Year: 1994

Plugging proposal received from Kirby Lillard

(company name) Sargent's Casing Pulling Inc. (phone) 316-624-7455

were: 5 1/2" at 3039' w/320 sx cement, CIBP AT 2710', Perfs at 2718-38, 2660-82,
Halco Easydrill at 2655', Open perfs at 2594-2604, 2626-34'

1st plug pump 1 sx hulls and 25 sx cement at perfs, pressure up,

2nd plug pump 50 sx cement at 1572', 3rd plug pump 45 sx cement at 650',

4th plug pump 10 sx cement at 40 to -4'.

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 1:30 p.m. Day: 22 Month: 12 Year: 1994

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 25 sx cement at perfs, pressured up,

2nd plug pumped 50 sx cement at 1572',

3rd plug pumped 45 sx cement at 650',

4th plug pumped 10 sx cement at 40 to -4'.

Mud between all plugs.

Remarks: Used common cement by Sargent's. Recovered 1572' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

observe this plugging.

INVOICED

DATE 1-9-95

INV. NO. 42018

12-22

Signed Glenn R. Barlow (TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
WICHITA, KS
JAN 9 4 1995