

To: 1 020670 5-4  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- Drilled 6/56 15-175-00245-  
C NE , SEC. 28 , T. 32 S, R 32 0000  
W/EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 5293  
Operator: Helmerich & Payne, Inc.  
Name & Address: P.O. Box 558  
Garden City, KS 67846

3960 feet from S section line  
1320 feet from E section line  
Lease Name Prater Well # 1  
County Seward 88.85  
Well Total Depth 2734 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 526

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Halliburton License Number \_\_\_\_\_  
Address Liberal, KS

Company to plug at: Hour: 9:45 a.m. Day: 4 Month: 5 Year: 19 93

Plugging proposal received from James Ford  
(company name) Helmerich & Payne, Inc. (phone) 316-276-3693

were: 4 1/2" at 2726', PBDT 2709', Perfs at 2610-2700, Open hole 2726-2734'  
1st plug spot 20 sx cement at 2150', 2nd plug pull to 1600' and spot 50 sx cement,  
3rd plug pull to 550' and spot 30 sx cement, 4th plug spot 5 sx cement at 10',  
5th plug pump 125 sx cement down 4 1/2" X 8 5/8" annulus.

Plugging Proposal Received by Glenn Barlow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 5:15 p.m. Day: 4 Month: 5 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug spotted 20 sx cement at 2150' through tubing,  
2nd plug pulled tubing to 1600' and spotted 50 sx cement,  
3rd plug pulled to 550' and spotted 30 sx cement, well went on vacuum,  
Tagged cement at 1244', 4th plug pulled to 558' and spotted 50 sx cement  
500 psi instant pressure on backside.

First plugs witnessed by Steve Middleton, last by Glenn Barlow.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. No casing recovery.  
(If additional description is necessary, use BACK of this report.)

Observe this plugging.

INVOICED  
DATE 5-18-93  
37237

Signed Glenn R Barlow  
(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION  
WICHITA, KS

MAY 12 1993  
CONSERVATION DIVISION  
WICHITA, KS