

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-175-20257-00-01  
Spot: SWNW Sec/Twnshp/Rge: 23-32S-32W  
3330 feet from S Section Line, 4620 feet from E Section Line  
Lease/Unit Name: FEDDER Well Number: A-1  
County: SEWARD Total Vertical Depth: 2737 feet

Operator License No.: 6230  
Op Name: FIRST NATIONAL OIL, INC.  
Address: 2340 TAMPA, STE H  
EL CAJON, CA 92020

Production Casing Size: 5.5 feet: 2825 WITH 50 SX CMT  
Surface Casing Size: 8.625 feet: 1719

\$88.95

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/02/2003 1:00 PM  
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.  
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: PUMP 400# HULLS & 25 SX CMT. PLUG AT 1750' WITH 50 SX CMT. PLUG AT 550' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: KEVIN STRUBE WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 04/03/2003 3:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:


CIBP @ 2697'. PERFS AT 2630-94'. PUMP 400# HULLS WITH 25 SX CMT. DISPLACE WITH MUD & PRESSURE TO 1000 PSIG & SHUT IN. 1ST PLUG PULL OUT OF HOLE TO 1750'. LOAD HOLE WITH MUD & PUMP 50 SX CMT. GOOD CIRCULATION. 2ND PLUG PULL OUT OF HOLE TO 550'. LOAD HOLE WITH MUD & PUMP 40 SX CMT. GOOD CIRCULATION. 3RD PLUG PULL OUT OF HOLE TO 40'. LOAD HOLE & PUMP 10 SX CMT TO SURFACE.

RECEIVED  
APR 11 2003  
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 2312' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Jim Holland  
(TECHNICIAN)

INVOICED

DATE 4-15-03

INV. NO. 2003061411

Form C/P 3