

1 110076

SEP 8 1987

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

85' API NUMBER 15- 175-20,969-0000
NE of
C NW SE, SEC. 19, T 32 S, R 32 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5476

2040 feet from S section line

Operator: DNB Drilling Inc.

1920 feet from E section line
Church of the

Name & Address

535 North Oliver

Lease Name Brethren Well # 1

County Seward 197.76

Wichita, KS 67208-4035

Well Total Depth 6085 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1628

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Cheyenne Drilling Inc. License Number 5382

Address P.O. Box 916, Garden City, KS

Company to plug at: Hour: 2:45 a.m. Day: 7 Month: 9 Year: 19 87

Plugging proposal received from Jack Pepper

(company name) Cheyenne Drilling Inc. (phone) 316-277-2062

were: to fill hole with heavy mud and spot cement through drill pipe. Elevation 2843'

1st plug at 2900' with 80 sx cement, 2nd plug at 1658' with 50 sx cement,

3rd plug at 725' with 25 sx cement, 4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 10 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by James R. Kapp
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 7:15 a.m. Day: 8 Month: 9 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 2900' with 80 sx cement,

2nd plug at 1658' with 50 sx cement,

3rd plug at 725' with 25 sx cement,

4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 10 sx cement,

6th plug to circulate mousehole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

SEP 10 1987

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.

(If additional description is necessary, use BACK of this form.)

Observe this plugging.

Signed James R. Kapp
(TECHNICIAN)

AKS

INVOICED
SEP 1 1 1987

DATE 18075
INV. NO. 9-8

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date 8 25 87
month day year

API Number 15-175-20,969-0000

OPERATOR: License # 5476
Name DNB Drilling, Inc.
Address 535 North Oliver
City/State/Zip Wichita, Ks. 67208-4035
Contact Person A. J. Jacques
Phone (316) 277-2062

85' NEC NW SE 19 Twp. 32 S, Rg. 32 East
2040 Ft. from South Line of Section
1920 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5382
Name Cheyenne Drilling, Inc.
City/State P.O. Box 916, Garden City, Ks.
Well Drilled For: Well Class: Type Equipment:
X Oil SWD Infield X Mud Rotary
X Gas Inj Pool Ext. Air Rotary
OWWO Expl X Wildcat Cable

Nearest lease or unit boundary line 600 feet
County Seward
Lease Name Church of the Brethren 1
Ground surface elevation 2843 feet MSL
Domestic well within 330 feet: yes no
Municipal well within one mile: yes no
Depth to bottom of fresh water 650 500
Depth to bottom of usable water 650 520
Surface pipe by Alternate: 1 X 2
Surface pipe planned to be set 1700'
Conductor pipe required NO
Projected Total Depth 6000' feet
Formation Mississippi

IF OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.
Date 8/20/87 Signature of Operator or Agent M. J. Brown Title Sec. Treas.

For KCC Use:
Conductor Pipe Required 2-21-88 feet; Minimum Surface Pipe Required 540 feet per Alt. 1 X
This Authorization Expires 2-21-88 Approved By M. J. Brown 8-21-87

Move in 8-26-87 set 1700' of 2 1/2" 10

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ Chase feet depth with 100 sxs of
2nd plug @ Base of Surface feet depth with 50 sxs of
3rd plug @ 700 feet depth with 25 sxs of
4th plug @ 40 to 0 feet depth with 10 sxs of
5th plug @ 10 feet depth with 10 sxs of
(2) Rathole with 10 sxs (b) Mousehole with 10 sxs

NOTE: Agreement between operator and

PUSHER JACK PEPPER
TD 6085 FORMATION St. Louis
SURFACE PIPE 8 7/8 @ 1628
ANHYDRITE ELEVATION 2843
STARTING TIME & DATE 2:45 AM 9-7-87
COMPLETION TIME & DATE 2:15 AM 9-8-
1st PLUG @ 2900 FT. W/ 80 SX
2nd PLUG @ 1658 FT. W/ 50 SX
3rd PLUG @ 725 FT. W/ 25 SX
4th PLUG @ 40-0 FT. W/ 10 SX
RAT HOLE CIRCULATED W/ 10 SX
MOUSE HOLE CIRCULATED W/ 10 SX
WATER WELL PLUGGED W/ Sand - SX
CEMENT COMPANY Halliburton
TECHNICIAN Dick Wagner saw all

RECEIVED
STATE CORPORATION COMMISSION

SEP 10 1987

CONSERVATION DIVISION
Wichita, Kansas