

1 020285

1-12

148
R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 175-21,089 - 0000

SE SE , SEC. 14 , T 32 S, R 32 (W)X

660 feet from S section line

660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3711

Lease Name McBride Well # 1-14

Operator: Shepler & Thomas, Inc.
Name &

County Seward 195.50

Address P.O. Box 2164

Well Total Depth 6000 feet

Evergreen, CO 80439

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1612

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Sargent's Casing Pullers License Number 6547

Address Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 2:30 p.m. Day: 10 Month: 1 Year: 19 90

Plugging proposal received from Kirby Lillard

(company name) Sargent's Casing Pullers (phone) 316-624-7455

were: 4 1/2" at 6000' PBTB 5948' Perfs at 5651-56' TOC 4650'

1st plug pump 1 sx hulls and 25 sx cement at perfs, displace with heavy mud,

2nd plug pump 50 sx cement at 1660-1460',

3rd plug pump 35 sx cement at 650-510',

4th plug pump 10 sx cement at 40-0'.

Plugging Proposal Received by Glenn R. Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 1:30 p.m. Day: 12 Month: 1 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 25 sx cement at perfs, displaced

with heavy mud,

2nd plug pumped 50 sx cement at 1660-1460',

3rd plug pumped 35 sx cement at 650-510',

4th plug pumped 10 sx cement at 40-0'.

Circulated hole with mud at cut off of pipe.

Remarks: Used common cement by Sargent's. Recovered 3323' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

(do not observe this plugging.)

DATE 1-29-90

Signed Glenn R. Barlow (TECHNICIAN)

INV. NO. 27232

1-12