

1 020795

8-29

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 175-21,041-0000
250' W of
NW NW, SEC. 7, T 32 S, R 32 W/X
4620 feet from S section line
4870 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5263

Lease Name Printz Well # 1-7

Operator: Midwestern Exploration Co.

County Seward

Name & Address P.O. Box 1884

Well Total Depth 6042 196.37 feet

Liberal, KS 67905-1884

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1605

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address P.O. Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 4 p.m. Day: 25 Month: 8 Year: 19 94

Plugging proposal received from Kirby Lillard

(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

Work: 5 1/2" at 2862' w/150 sx cement, TOC 2465', PBTD 2860', Perfs at 2664-68, 2694-98, 2725-30'

1st plug pump 2 sx hulls and 25 sx cement to bottom,

2nd plug pump 50 sx cement at 1630',

3rd plug pump 40 sx cement at 800',

4th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part X None _____

Operations Completed: Hour: 5:15 p.m. Day: 29 Month: 8 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 25 sx cement at perfs,
tagged cement at 2600',

2nd plug pump 50 sx cement at 1630',

3rd plug pumped 40 sx cement at 800',

4th plug pumped 10 sx cement at 40 to -2'.

Gel mud between all plugs.

Remarks: Used common cement by Sargent's. Recovered 2435' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

Observe this plugging.

INVOICED

SEP 12 1994

DATE _____

WV. NO. 41193

Signed Glenn R. Barkan
(TECHNICIAN) 1994

RECEIVED
STATE CORPORATION COMMISSION

CONSERVATION DIVISION
WICHITA, KANSAS FORM C
Rev.