

To: R 1 020877 6-15
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- NA
NW NE NW, SEC. 6, T 32 S, R 32 W/EX
4950 feet from S section line
3630 feet from E section line
Lease Name Cotton Well # A-2
County Seward 183.56
Well Total Depth 5648 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1618

TECHNICIAN'S PLUGGING REPORT
Operator License # 5447
Operator: OXY USA INC.
Name & Address P.O. Box 26100
Oklahoma City, OK 73126-0100

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent & Horton Plugging Inc. License Number 31151

Address Rt. 1, Box 49BA, Tyrone, OK 73951-9731

Company to plug at: Hour: 10 a.m. Day: 15 Month: 6 Year: 19 95

Plugging proposal received from Don Horton

(company name) Sargent & Horton Plugging Inc. (phone) 405-854-6515

Size: 4 1/2" at 5648', TOC 3823'

1st plug set CIBP at 4587' with 3 sx cement on top,

2nd plug pump 40 sx cement at 2620',

3rd plug pump 50 sx cement at 1640', 4th plug pump 25 sx cement at 720',

5th plug pump 10 sx cement at 40 to -4'.

Plugging Proposal Received by Glenn Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:30 p.m. Day: 15 Month: 6 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4587' with 3 sx cement on top.

Shot pipe at 2800-01'. Could not pull.

2nd plug pumped 40 sx cement at 2620',

3rd plug pumped 50 sx cement at 1640',

4th plug pumped 25 sx cement at 720',

5th plug pumped 10 sx cement at 40 to -4'. All plugs displaced with gel mud.

Remarks: Used common cement by Sargent & Horton. Recovered 2620' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

Observe this plugging.

DATE 6-29-95

WV. NO. 43005
6-15

Signed Glenn Barlow
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION
JUN 21 1995
CONSERVATION DIVISION
WICHITA, KS