

1 051878 12-23

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 175-21,285-0000

SW SE NE, SEC. 4, T 32 S, R 32 W EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 30606  
Operator: Murfin Drilling Company, Inc.  
Name & Address: 250 N. Water, Ste. 300  
Wichita, KS 67202

2970 feet from S section line  
990 feet from E section line

Lease Name Wessler Well # 1-4  
County Seward  
Well Total Depth 6000 195.00 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 1660

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Mike's Testing & Salvage Inc. License Number 31529  
Address P.O. Box 209, Chase, KS 67524

Company to plug at: Hour: 9:30 a.m. Day: 23 Month: 12 Year: 19 94

Plugging proposal received from Richard McIntyre  
(company name) Mike's Testing & Salvage Inc. (phone) 316-938-2943

were: 5 1/2" at 5986' w/300 sx cement, PBTD 5510', Perfs at 4840-42, 4719-22'  
1st plug sand back to 4660' and dump 5 sx cement on top of sand through bailer,  
2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release  
8 5/8" wiper plug and pump 175 sx cement.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None \_\_\_\_\_ X

Operations Completed: Hour: 11:15 a.m. Day: 23 Month: 12 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug sanded back to 4660' and dumped 5 sx cement on top of sand  
through bailer,  
2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls,  
released 8 5/8" wiper plug and pumped 175 sx cement.  
Maximum pressure 600 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2800' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

(XXXXX) observe this plugging.

Signed Richard W. Lacey  
(TECHNICIAN)

INVOICED  
DATE 1-9-95  
INV. NO. 42019