

To: 1 090781 3-6
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-175-21,601 - 0000
NE, SEC. R 3, T 32 S, R 32 W/E
4030 feet from S section line
1700 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 31836
Operator: St. Mary Operating Company
Name: 1776 Lincoln St., Ste. 1100
Address: Denver, CO 80203

Lease Name Roehr Well # 1
County Seward 91.00
Well Total Depth 2800 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 559

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ O&A X
Other well as hereinafter indicated _____

Plugging Contractor Abercrombie RTD, Inc. License Number 30684
Address 150 N. Main, Ste. 801, Wichita, KS 67202-1383

Company to plug at: Hour: _____ Day: 6 Month: 3 Year: 19 97
Plugging proposal received from Bill Craig
(company name) Abercrombie RTD, Inc. (phone) 316-262-1841

Work: to fill hole with heavy mud and spot cement through drill pipe
1st plug at 1600' with 50 sx cement, 2nd plug at 590' with 50 sx cement,
3rd plug at 40' with 10 sx cement,
4th plug to circulate rathole with 15 sx cement,
5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X
Operations Completed: Hour: 5:30 a.m Day: 6 Month: 3 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug at 1600' with 50 sx cement,
2nd plug at 590' with 50 sx cement,
3rd plug at 40' with 10 sx cement,
4th plug to circulate rathole with 15 sx cement,
5th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

~~xxxxx~~ (did not) observe this plugging.

INVOICED
DATE 3-12-97
INV. NO. 47735
3-6

Signed [Signature]
(TECHNICIAN)

RECEIVED
KANSAS COMB. COM.
MAY 19 10 31 AM '97

EFFECTIVE DATE 8-17-97

Starting Date 02 29 97
month day year

API Number 15 - 175-216010000

OPERATOR: License # 31836
Name St. Mary Operating Company
Address 1776 Lincoln St., Suite 1100
City/State/Zip Denver, Co. 80203
Contact Person Bob Bachman
Phone 303-863-4327

IS SECTION X REGULAR IRREGULAR
NE/4 Sec. 3 Twp. 32 S. Rg. 32. W
4030 Ft. from South Line of Section
1700 Ft. from East Line of Section

CONTRACTOR: License # 30684
Name Abercrombie RTO, Inc.
City/State

NOTE: Attach acreage attribution plat locating both Chase (Hugoton) wells
Total number of acres attributed to unit 640

Well Drilled as: X New Recompletion OWWO

Nearest producing well from same common source of supply 2260 feet
Nearest lease or unit boundary line 1250 feet

Projected Total Depth 3000 feet
Formation Chase

County Seward
Lease Name Roehc Well # 1

If OWWO or Recompletion: old well info as follows:
Operator
Well Name
Comp. Date Old Total Depth

Ground surface elevation 2833 feet MSL
Depth to bottom of fresh water 200 410
Depth to bottom of usable water 450 500

Surface pipe by Alternate:
Surface pipe planned to be set 550' ± (X 2X ALT. ONLY)

Water Source for Drilled Operations:
DWR Permit #: well farm pond X other

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.
Date 10 February 1997 Signature of Operator or Agent Title Vice President

For KCC Use:
Conductor Pipe Required NONE feet; Minimum Surface Pipe Required 550' feet per Alt. (1) X
This Authorization Expires 8-17-97 Approved By JK 8-17-97

9/95

RECEIVED
KANSAS CORP COMM
1997 APR 10 3:49

usher Bill Craig
POD DATE 2-28-97 INIT. R.C.
LENGTH SURFACE PLANNED 550'

RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.
ATHOLED AHEAD? Y N SIZE HOLE
URFACE PIPE 8 1/2 @ 559 CONDUCTOR
NHYDRITE T- B- ELEVATION

D 2800' FORMATION
AN PIPE @ SX DV TOOL ALT II DONE SX Y N
Arbuckle Plug @ Ft. W/ SX
Hug./Council @ Ft. W/ SX
Anhydrite Base @ 1600 Ft. W/ 50 SX
1/2 Base Anyh. @ Ft. W/ SX
1/2, 1/2 Plug @ Ft. W/ SX
Bottom Surface @ 590 Ft. W/ 50 SX
40' Plug @ 40 Ft. W/ 10 SX
AT HOLE CIRC/W 15 SX MOUSE HOLE W/ 10 SX

WATER WELL SX (Irr. Well Pond Hauling)
TECHNICIAN Sam DATE 3-5-97
TYPE OF CEMENT 60/40 60/40 60/40
PARTING TIME : (AM/PM) DATE
COMPLETION TIME 5:30 (AM/PM) DATE 3-6-97
EMENT COMPANY Allied