

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Eagle Creek Corporation

ADDRESS 107 N. Market #411 Wichita, Ks. 67202

PHONE#(316) 264-8044 OPERATORS LICENSE NO. 30129

Character of Well dry

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Well Completed 2-10-94

Plugging Commenced 3-10-94

Plugging Completed 3-11-94

The plugging proposal was approved on 3-9-94 (date)

by District #2 (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? with CP-1

Producing Formation Miss. Depth to Top 3669 Bottom 3790 T.D. 3790

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	water	0	726	8 5/8	726	none
	Water	0	3835	5 1/2	3835	2650

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each section sand back to 25, spot 5 sx cement, pull pipe at 2650 ft. pull to 765 ft. and pump 35 sx plug. pull to 360 ft. and pump 25 sx plug. pull to 90 ft. and pump 25 sx plug to surface. United Cementing # 4850

Name of Plugging Contractor VAL Energy, Inc. License No. 5822

Address Box 322 Haysville, Ks. 67060

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Eagle Creek Corporation

STATE OF Kansas COUNTY OF Sedgwick, ss.

K. Todd Allam / Agent for Operator (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed in the same are true and correct, so help me God.

(Signature) K Todd Allam

(Address) Wichita, Ks.

RECEIVED
KANSAS CORPORATION COMMISSION

MAR 15 1994 SUBSCRIBED AND SWORN TO before me this 15th day of March, 1994

Gary D. Stearns
Notary Public

CONSERVATION DIVISION
WICHITA, KS My Commission Expires: 2-19-96
USE ONLY ONE SIDE OF EACH FORM

