

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

Sedgwick County, Sec. 30 Twp. 29S Rge. 2W (E) (W)

Location as "NE/CNWxSWx" or footage from lines SE NE NE

Lease Owner The Texas Company

Lease Name A. A. Parsons Well No. 1

Office Address 614 Bitting Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry

Date well completed February 4 19 55

Application for plugging filed (2-4-55, verbal) February 7 19 55

Application for plugging approved February 4 19 55

Plugging commenced February 4 19 55

Plugging completed February 5 19 55

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. S.S. Greider

Producing formation Depth to top Bottom Total Depth of Well 4100 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4"	539'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

PLUGGED AS FOLLOWS:

- 4100' to 480' - Heavy Mud
- 480' to 440' - 20 Sacks Cement
- 440' to 30' - Heavy Mud
- 30' to Surface - 15 Sacks Cement

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Stickle Drilling Company

Address Box 117, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
M. C. Harrell (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) M. C. Harrell

614 Bitting Building, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 7th day of February, 19 55

My commission expires September 20, 1956

Notary Public.

PLUGGING
FILE SEC 30 TWP 29S RGE 2W
BOOK PAGE 25 LINE 18

RECEIVED
STATE CORPORATION COMMISSION
MAY 10 1955 3-18-55
CONSERVATION DIVISION
Wichita, Kansas

The Texas Company
Tulsa, Oklahoma

Tulsa, Oklahoma
February 11, 1955

CONTRACTOR: Stickle Drilling Company
Drilling Commenced: January 13, 1955
Drilling Completed: February 5, 1955

A. A. Parsons #1 SE-NE-NE
Section 30-29S-2W, Sedgwick
County, Kansas.

DRILLERS LOG

Sand	0-140
Shale & Shells	140-530
Shale	530-540
Lime Anhydrite	540-570
Shale, Sand & Shells	570-770
Shale & Lime	770-940
Lime	940-1070
Shale & Lime	1070-1200
Lime & Shale	1200-1460
Shale & Lime	1460-2131
Lime & Shale	2131-2380
Shale & Lime	2380-2710
Shale	2710-2737
Sand	2737-2857
Shale & Lime	2857-2985
Lime	2985-3047
Lime & Shale	3047-3073
Lime	3073-3203
Lime & Shale	3203-3237
Lime	3237-3286
Shale & Lime	3286-3349
Lime & Shale	3349-3401
Shale & Lime	3401-3648
Lime	3648-3672
Lime & Shale	3672-3697
Lime	3697-3751
Shale	3751-3777
Shale & Lime	3777-3807
Lime & Shale	3807-3932
Lime	3932-3962
Lime & Shale	3962-4015
Shale & Lime	4015-4048
Lime	4048-4090
Sand & Shale	4090-4095
Sand	4095-4100 T.D.

I, Frank E. Stickle hereby certify the above to be a true and complete Drillers Log of The Texas Company's A. A. Parsons #1 SE-NE-NE-Section 30-29S-2W, Sedgwick County, Kansas.

Frank E. Stickle
Frank E. Stickle

William T. Bonham
Notary Public
February 13, 1956
My Commission Expires

PLUGGING
FILE REC 30-29 S 2W
BOOK PAGE 25 LINE 16

LOG OF WELL

FORM PO-214 SHEET 1 (4-54) 35M

A. A. PARSONS NO. 1

SHEET 1

OWNER The Texas Company DIVISION Oklahoma DATE MADE March 10, 1955
 DISTRICT Kansas LEASE A. A. Parsons WELL NO. 1
 STATE Kansas COUNTY OR PARISH Sedgwick TWP. 29S RANGE 2W SEC. 30
 LOCATION OF WELL SE NE NE

COMMENCED RIGGING UP 1-13-55 COMMENCED DRILLING 1-14-55 COMPLETED DRILLING 2-5-55
 DAY DRILLER _____ NIGHT DRILLER _____ CONTRACTOR Stickle Drilling Co.
 CABLE FROM _____ TO _____ ROTARY FROM 0' TO 4100' COMPANY RIG No. _____
 TOTAL DEPTH 4100' MEASURED BY M. C. Harrell ELEVATION KB - 1284
DE - 1281
GL - 1275

CASING RECORD

SIZE	WEIGHT	PUT IN WELL		PULLED OUT		LOST IN WELL		SHOES		PACKERS		
		FEET	INS.	FEET	INS.	FEET	INS.	LENGTH	MAKE	KIND	LENGTH	SET AT
10-3/4"	32.75#	539'						(R-2, H-40, new casing)				FT.
												FT.
												FT.
												FT.
												FT.
												FT.
												FT.
												FT.
												FT.
10-3/4" casing set at 530' with 450 sacks cement, 3 sacks CC, 100# flocele.												FT.
Cement circulated.												FT.

WAS CASING CEMENTED? _____ IF SO, HOW MANY SACKS OF CEMENT USED? _____
 LINER: STATE SIZE AND WEIGHT _____ WHERE SET _____ FT. AND INS. BLANK _____ FT. AND INS. PERFORATED _____
 HOW PUT TOGETHER _____ COUPLING _____ FLUSH-JOINT _____ INSERTED _____
 REMARKS: _____

EQUIPMENT RECORD

TUBING				SUCKER RODS			PUMPING OUTFIT
SIZE	WEIGHT	FEET	INS.	FEET	INS.	SIZE AND KIND	DESCRIPTION, KIND, SIZE, ETC.
Completed Plugging 2-5-55							

FLOWING, PUMPING, GASSER OR DRY Dry PRODUCTION FIRST 24 HOURS _____ PRODUCTION SETTLED _____
 IF GAS WELL, OPEN FLOW CAPACITY _____ SHUT IN PRESSURE _____ ROCK PRESSURE _____
 KIND OF SHOT _____ SIZE OF SHOT, QUARTS _____
 NUMBER OF SHELLS _____ SIZE OF SHELLS _____ INCHES, DIAMETER _____
 LENGTH OF SHELLS _____ FEET _____ INCHES _____ TOP OF SHOT _____
 BOTTOM OF SHOT _____ ANCHOR _____ WELL BRIDGED TO _____
 TOTAL DEPTH OF WELL _____ NUMBER OF SHOT _____ PRODUCTION BEFORE SHOT _____ BBLs. PER DAY _____
 PRODUCTION AFTER SHOT _____ BBLs. PER DAY: SHOT FURNISHED BY _____
 NAME OF SHOOTER _____ SHOT INSPECTED _____ BY _____ (COMPANY EMPLOYEE)
 COMMENCED DRILLING DEEPER _____ COMPLETED _____ DRILLING DEEPER _____
 TOTAL DEPTH _____ PRODUCTION FIRST 24 HOURS _____ PRODUCTION SETTLED _____
 REMARKS: _____

A. A. Parsons #1
 Rank - Wildcat
 TD 4100'
 Completed Drilling 2-5-55
 Completed Plugging 2-5-55

NOTE: IF WELL WAS DRY, STATE UNDER REMARKS, WHEN, HOW, AND BY WHOM PLUGGED.
 STATE UNDER REMARKS ANYTHING OF INTEREST NOT COVERED IN LOG.
 IF THE SPACE PROVIDED FOR REMARKS IS NOT SUFFICIENT WRITE ON BOTTOM OF LAST SHEET OF LOG.

PLUGGING
 FILE SEC 30 129 27W
 BOOK PAGE 95 LINE 16

TOTAL NUMBER OF SHEETS _____

LOG OF WELL

SHEET No. 2

District Kansas Owner The Texas Company Farm A. A. Parsons Well No. 1

FORMATION	AMOUNT	COLOR	HARD OR SOFT	DEPTH CORES TAKEN	REMARKS
REMARKS:					
1-23-55					Ran DST #1 from 3027-47', open 1 hour, recovered 145' muddy salt water, IFP 40#, FFP 95#, SIBHP 1100# in 20 minutes.
1-24-55					Ran DST #2 from 3053-73', open 1 hour, had good blow, recovered 210' muddy salt water, SIBHP 1133# in 20 minutes.
1-25-55					Ran DST #3 from 3114-25', open 1 hour, recovered 280' muddy salt water. IFP 40#, FFP 140#, SIBHP 1210# in 20 minutes.
1-29-55					Ran DST #4 from 3639-48', open 1 hour, recovered 90' watery mud, IFP 15#, FFP 32#, SIBHP 1190# in 30 minutes. Ran DST #5 from 3652-72', open 1 hour, recovered 75' mud. IFP 16#, FFP 47#, SIBHP 1440# in 30 minutes.
2-3-55					Took Core #1 from 4080-85', recovered 5'.
2-5-55					Ran DST #6 from 4076-85', open 2 hours, recovered 50' watery mud and 120' muddy salt water. IFP 14#, FFP 70#, SIBHP 1610# in 30 minutes.
					Drilled to 4100' in sand. Ran Schlumberger Survey. Well non-commercial. Plugged and abandoned.
					TOPS:
					Topeka-----1988
					Heebner-----2412
					Toronto-----2442
					Stalnaker-----2731
					Kansas City-----3021
					Base Kansas City----3232
					Marmaton-----3313
					Cherokee-----3450
					Mississippi-----3630
					Kinderhook-----4010
					Simpson-----4079

PLUGGING
 FILE DEC 30 1955
 PAGE 95 LINE 18

MAR 1 1956
 GEOLOGICAL SURVEY DIVISION
 WASHINGTON, Kansas