


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
241 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Stevens County, Sec. 13 Twp. 31-S Rge. (E) 35 (W)

Location as "NE/CNW/SW" or footage from lines SE/4 SE/4
Lease Owner Martin & Keller
Lease Name L. Black Well No. 1
Office Address 1430 Terrace Drive - Tulsa, Oklahoma 74104
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed October 25 1968
Application for plugging filed November 19 68
Application for plugging approved 19
Plugging commenced October 25 1968
Plugging completed October 25 19 68
Reason for abandonment of well or producing formation Dry hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Edgar J. Eves
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	sand & red bed	0'	1363'	8-5/8"	1367'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Spot 35 sx. cement and plug at 1250' - 1350'
Spot 15 sx. cement and plug at 0' - 40'

RECEIVED
STATE CORPORATION COMMISSION
NOV 15 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Rine Drilling Company, Inc.
Address Suite 600 - 300 West Douglas - Wichita, Kansas 67202


STATE OF OKLAHOMA, COUNTY OF TULSA, ss.

Cecil M. Keller, (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Cecil M. Keller

(Address)

SUBSCRIBED AND SWORN to before me this 14th day of November, 1968



Aldine Qualls

Notary Public.

My commission expires April 21, 1971

15-189-20019-0000

RECEIVED
STATE CORPORATION COMMISSION

NOV 15 1968

CONSERVATION DIVISION
Wichita, Kansas

SE SE
SECTION 13-31S-35W
STEVENS COUNTY, KANSAS

L. BLACK WELL NO. 1

CONTRACTOR: RINE DRILLING COMPANY, INC.

STARTED: OCTOBER 13, 1968

COMPLETED: OCTOBER 25, 1968

	<u>L</u>	<u>O</u>	<u>G</u>	
Clay-Sand	0'	-	515'	
Sand n	515'	-	805'	
Red Bed	805'	-	1363'	Totco - 1/4° @ 927'
Sand & Red Bed	1363'	-	1663'	Run 425 jts. 8 5/8 24# new csg. 1367'
Red Bed	1663'	-	2072'	set @ 1363' cement w/675 sx. lite wt.
Red Bed & Anhydrite	2072'	-	2310'	2% cc + 150 sx. com. w/3% cc
Shale & Lime	2310'	-	2745'	Totco - 1° @ 2339'
Lime	2745'	-	2878'	Totco - 3/4° @ 2770'
Lime & Shale	2878'	-	3034'	
Lime	3034'	-	3590'	
Lime w/chalk strks.	3590'	-	3800'	
Lime	3800'	-	3942'	
Lime & Sand Chert	3942'	-	4080'	
Lime	4080'	-	4598'	
Lime & Shale Strks.	4598'	-	4610'	Totco - 1° @ 4610'
Lime	4610'	-	5770'	Snot 35 sx. plug @ 1250'-1350'
				Snot 15 sx. plug @ 0-40'

STATE OF KANSAS)
COUNTY OF SEDGWICK) ss

I, R. M. Green, do hereby certify that the above is a true and accurate log of the L. Black Well No. 1, located SE of SE of SEction 13-31S-35W, Stevens County, Kansas.


R. M. Green, Secretary-Treasurer

Subscribed and sworn to before me this 30th day of October, 1968.




Loren E. Lake, Notary Public

My Commission Expires: 6/14/70