

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-189-21,601-0000

LEASE NAME Moorhead "C"

WELL NUMBER 3

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

1980 Ft. from S Section Line

4620 Ft. from E Section Line

LEASE OPERATOR Anadarko Petroleum Corporation

SEC. 13 TWP. 31S RGE. 35 (X) or (W)

ADDRESS P. O. Box 351, Liberal, KS 67905-0351

COUNTY Stevens

PHONE# (316) 624-6253 OPERATORS LICENSE NO. 4549

Date Well Completed 2-16-94

Character of Well D&A

Plugging Commenced 2-16-94

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 2-16-94

The plugging proposal was approved on 2-16-94 (date)

by Verbal (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? -

Producing Formation None Depth to Top None Bottom None T.D. 5775

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	1728	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Spotted 100 sxs cmt plug @ 3100, 50 sxs plug @ 1790, 40 sxs plug @ 600, 10 sxs plug 0-40, 15 sxs in rathole, 10 sxs in mousehole. Cmt 60/40 Poz, 6% gel. Heavy drlg mud pumped between each plug. Restore location.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Gabbert-Jones, Inc. License No. 5842

Address 333 East English, Wichita, Kansas 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Anadarko Petroleum Corporation

STATE OF Kansas COUNTY OF Seward, ss.

Beverly J. Williams, Technical Assistant (Employee of Operator) or ~~owner~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Beverly J. Williams

(Address) Beverly J. Williams, Tech. Asst.
P.O. Box 351, Liberal, KS 67905-0351

SUBSCRIBED AND SWORN TO before me this 8th day of March 1994

C Cheryl Steers
Notary Public

My Commission Expires:



RECEIVED
STATE CORPORATION COMMISSION
10 1994
Form CP-4
Revised 05-88
Wichita, Kansas