

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Stevens County, Sec. 12 Twp. 31S Rge. (E) 35 (W)

Location as "NE/CNW/SW" or footage from lines C NE NW
Lease Owner Mobil Oil Corporation
Lease Name George B. Strong Unit Well No. 6
Office Address P. O. Box 1934, Oklahoma City, Oklahoma 73101
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed September 1 1962
Application for plugging filed August 20 1973
Application for plugging approved August 22 1973
Plugging commenced October 25 1973
Plugging completed October 26 1973
Reason for abandonment of well or producing formation Uneconomical to produce.



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Edgar Eves
Producing formation Mississippian Depth to top 5525' Bottom 5626' Total Depth of Well 5690 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Mississippian-Chester	Oil	5563'	5572'	8-5/8"	641'	None
				4 1/2"	5678'	1822'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Placed 20 sack cement plug on bottom, top of cement at 5400'. Shot 4 1/2" casing at 1822', casing free. Placed 35 sack cement plug 644' - 544'. Placed 15 sack cement plug in top of 8-5/8" surface casing from 45' - 0'. Cut off 8-5/8" surface casing 3' below ground level and welded a steel plate across the top of the 8-5/8" casing.

RECEIVED
STATE CORPORATION COMMISSION
NOV 14 1973
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Sargents Casing Pulling Service
Address 620 South Lincoln, Liberal, Kansas 67901

STATE OF Oklahoma, COUNTY OF Oklahoma, ss.
Paul K. Langenberg (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Paul K. Langenberg, Office Group Supervisor
P. O. Box 1934, Oklahoma City, Okla. 73101
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of November, 1973

Richard N. Squibb
Notary Public.

My commission expires November 17, 1977

15-189-10042-0000

WELL LOG

RECEIVED
SEP 12 1962

COMPANY MOBIL OIL COMPANY

SEC. 12 T. 31S R. 35W

FARM STRONG UNIT NO. 6

LOC. C-NE, NW


TOTAL DEPTH 5690'

COUNTY STEVENS CO., KANSAS

COMM. August 12, 1962 COMP. August 29, 1962

CONTRACTOR GARVEY DRILLING COMPANY

CASING 8-5/8" @ 644' w/400 sax.
4 1/2" @ 5680' w/150 sax.



ELEVATION

RECEIVED
STATE CORPORATION COMMISSION
AUG 22 1963
CONSERVATION DIVISION
Wichita, Kansas

FIGURES INDICATE BOTTOM OF FORMATIONS

350	Shale & sand
645	Shale & red bed
740	Red bed
1553	Red bed & sand
2175	Shale & shells
2365	Shale & lime
2922	Lime & shale
3141	Lime
3425	Lime & chalk
3785	Shale & lime
3995	Chalky lime & shale
4062	Shale & lime
4205	Lime & shale
4867	Lime
4945	Lime & shale
5362	Lime
5520	Lime & shale
5525	Lime
5690	Lime & shale
5690	T. D.

State of KANSAS
County of BARTON

I, VERNE A. MORRIS of GARVEY DRILLING COMPANY

upon oath state the above and foregoing is a true and correct copy of the log of the #6 STRONG UNIT well.

Verne A. Morris

Subscribed and sworn to before me this 5th day of September 1962.

My Commission Expires: November 12, 1962

Brantley
NOTARY PUBLIC