


STATE OF KANSAS
CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

STEVENS County. Sec. 12 Twp. 31S Rge. 35 (B) (W)
Location as "NE/CNW/SW" or footage from lines C SW NW
Lease Owner MOBIL OIL COMPANY
Lease Name G. B. STRONG Well No. 1
Office Address 300 NORTH BROADWAY, WICHITA, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed 7-24-61 19__
Application for plugging filed PHONE 7-24-61, LETTER 10-27-61 19__
Application for plugging approved 7-24-61 19__
Plugging commenced 7-24-61 19__
Plugging completed 7-24-61 19__
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19__
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well FRANK BROADFOOT
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3718 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	3-5/8" 641'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

FILLED HOLE WITH HEAVY MUD TO 2790 FEET. SET FIRST PLUG OF 135 SACKS CEMENT 2790 TO 2390'

FILLED HOLE WITH HEAVY MUD TO 660 FEET. SET SECOND PLUG OF 30 SACKS CEMENT 660' TO 564'

FILLED HOLE WITH HEAVY MUD TO 40 FEET. SET THIRD PLUG OF 15 SACKS CEMENT FROM 40 FEET TO SURFACE.

RECEIVED
STATE CORPORATION COMMISSION
OCT 31 1961
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor GABBERT-JONES DRILLING CO., INC.
Address 514 ORPHEUM BLDG., WICHITA 2, KANSAS

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
E. E. HALL (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) E. E. Hall

514 ORPHEUM BLDG., WICHITA, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 27TH day of OCTOBER, 1961

Vira A. McKenzie
VIRA A. MCKENZIE Notary Public.

My commission expires OCTOBER 2, 1963



15-189-10076-0000

GABBERT-JONES DRILLING CO., INC.
WICHITA, KANSAS
DRILLERS WELL LOG

G. B. STRONG #1
C SW NW SECTION 12-31S-35W
STEVENS COUNTY, KANSAS


COMMENCED: JULY 5, 1961
COMPLETED: JULY 24, 1961

OPERATOR - MOBIL OIL COMPANY

DEPTH		FORMATION	REMARKS
FROM	TO		
0	95	SURFACE CLAY & SAND	
95	395	SAND	
395	585	SHALE	
585	640	RED BED	RAN 641' OF 8-5/8" CASING, SET @ 640' W/425 SACKS CEMENT.
640	1220	RED BED	
1220	1415	SAND	
1415	1640	RED BED	
1640	2000	RED BED & SHALE	
2000	2352	SHALE & SHELLS	
2352	2710	LIME	
2710	2829	SHALE & LIME	
2829	2877	LIME	
2877	2994	LIME & SHALE	
2994	3167	LIME	
3167	3312	LIME & SHALE	
3312	3418	LIME	
3418	3490	LIME & CHALK	
3490	3718	LIME & SHALE	
3718	TD		DRY & ABANDONED

ST
OCT 27 1961
CONSERVATION DIVISION
Wichita, Kansas

I, E. E. HALL, CERTIFY THIS IS A TRUE AND CORRECT COPY OF THE DRILLER'S WELL LOG FOR THE WELL DRILLED IN THE C, SW NW SECTION 12-31S-35W, STEVENS COUNTY, KANSAS, TO THE BEST OF MY KNOWLEDGE AND BELIEF.


E. E. HALL

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 27TH DAY OF OCTOBER, 1961, PERSONALLY APPEARED E. E. HALL TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.

MY COMMISSION EXPIRES OCTOBER 2, 1963


VIRA A. MCKENZIE, NOTARY PUBLIC