

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-62-3-117

API NUMBER 15-175-21117-00-01

LEASE NAME Dreitz Farms OWWO

WELL NUMBER 1-4

2962 Ft. from S Section Line
386 Ft. from E Section Line

SEC. 4 TWP. 32 SRGE. 33 (E) or (W)

COUNTY Seward

Date Well Completed 01/15/90

Plugging Commenced 02/19/03

Plugging Completed 02/19/03

RECEIVED
JUN 30 2003
KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Chesapeake Operating, Inc.

ADDRESS P. O. Box 18496, Oklahoma City, OK 73154-0496

PHONE# (409) 848-8000 OPERATORS LICENSE NO. 32334

Character of Well OWWO

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11/12/02 (date)

by _____ (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Morrow/Chester Depth to Top 5528-5702 Bottom 5702 T.O. 5952'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put in | Pulled out |
|-----------|---------|------|----|-------|--------|------------|
| | | | | 8-5/8 | 1608 | |
| | | | | 4-1/2 | 5768 | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from ___ feet to ___ feet each set: MIRU Log-Tech, Inc., set CIBP @1653', load 4-1/2" csg to 500#, held OK, RH, perforate @1630', RDMO Log Tech, MIRU Allied - mix 375 sx 64:40 Poz + additive, circ to surface, SIW, RDMO Allied, well P&A'd 02/19/03

Name of Plugging Contractor Allied Cementing Co., Inc. License No. _____

Address P. O. Box 31, Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Chesapeake Operating, Inc.

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

Barbara J. Bale (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Barbara J. Bale *Barbara J. Bale*

(Address) P. O. Box 18496, Okla. City, OK 73154-0496

SUBSCRIBED AND SWORN TO before me this 27th day of June, 2003

Sarah J. Caldwell 00019692
Notary Public

My Commission Expires: 11/29/04

NOTARY SEAL
SARAH CALDWELL
Oklahoma County
Notary Public in and for
State of Oklahoma
My commission expires Nov. 29, 2004.

May-03-03 09:40A

P.04

ALLIED CEMENTING CO., INC. 11965

Federal Tax I.D.# 48-0727860

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:

Oakley

| | | | | | | | |
|-------------------------|-------------------|---|------------------|------------|----------------------------|--------------------------|----------------------------|
| DATE <u>2/19/03</u> | SEC. <u>4</u> | TWP. <u>32c</u> | RANGE <u>33w</u> | CALLED OUT | ON LOCATION <u>8:30 AM</u> | JOB START <u>9:00 AM</u> | JOB FINISH <u>11:30 AM</u> |
| PROJECT <u>12 Ferns</u> | WELL # <u>6-4</u> | LOCATION <u>Sublette 75 2w 5 1/2 s w 15</u> | | | COUNTY <u>Seward</u> | STATE <u>KS</u> | |

OLD OR NEW (Circle one)

CONTRACTOR _____ OWNER S&W

TYPE OF JOB O.H.P

HOLE SIZE _____ TD _____

CASING SIZE 4 1/2 DEPTH 11 1650

TUBING SIZE _____ DEPTH _____

DRILL PIPE _____ DEPTH _____

TOOL _____ DEPTH _____

PRES. MAX 500 MINIMUM 50

MEAS. LINE _____ SHOE JOINT _____

CEMENT LEFT IN CSG. _____

PERFS. 1630

DISPLACEMENT _____

CEMENT AMOUNT ORDERED

375 sks 60/40 + 672 gal.

| | | | | |
|----------|-----------------|---|--------------|----------------|
| COMMON | <u>225 sks</u> | @ | <u>7.85</u> | <u>1766.25</u> |
| POZ MIX | <u>150 sks</u> | @ | <u>3.55</u> | <u>532.50</u> |
| GEL | <u>20 sks</u> | @ | <u>10.00</u> | <u>200.00</u> |
| CHLORIDE | | @ | | |
| | | @ | | |
| | | @ | | |
| | | @ | | |
| | | @ | | |
| HANDLING | <u>375 sks</u> | @ | <u>1.10</u> | <u>412.50</u> |
| MILEAGE | <u>48/51 mi</u> | | | <u>450.00</u> |

EQUIPMENT

PUMP TRUCK CEMENTER Max

300 HELPER Terry

BULK TRUCK

361 DRIVER Jarrod

BULK TRUCK

_____ DRIVER _____

RECEIVED

JUN 30 2003

TOTAL 3361.25

REMARKS:

KCC WICHITA

SERVICE

Set O.P. Load 4 1/2 Pressure To 500 PSK
 Perf. 4 1/2 @ 1630 Hookup To 4 1/2 csg
 Mix 375 sks cement Circulate cmf
 To surface. Shut down

DEPTH OF JOB 1630

PUMP TRUCK CHARGE _____ 475.00

EXTRA FOOTAGE _____ @ _____

MILEAGE 30 mi @ 3.00 90.00

PLUG _____ @ _____

TOTAL 565.00

CHARGE TO: Chesapeake Operating Inc

STREET _____

CITY _____ STATE _____ ZIP _____

FLOAT EQUIPMENT

_____ @ _____

_____ @ _____

_____ @ _____

_____ @ _____

TOTAL _____

To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX _____

TOTAL CHARGE _____

DISCOUNT _____ IF PAID IN 30 DAYS

SIGNATURE Dennis Frick

Dennis Frick
 PRINTED NAME