

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

* Revised:
Changed plugging contractor

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-191-21415-0000 (of this well)
(This must be listed; if no API# was issued, please note drilling completion date.)

8/89
LEASE OPERATOR Pluggers, Inc. OPERATORS LICENSE NO. 3909

ADDRESS P.O. Box 782050 Wichita, KS 67278 PHONE # (316) 636-4390

LEASE (FARM) Eriess SWD WELL NO. 2-A WELL LOCATION 1650' FSL } SW 1/4 COUNTY Sumner
1200' FWL }

SEC. 29 TWP. 30 RGE. 3W (E or (W)) TOTAL DEPTH 4478' PLUG BACK TO 4280'

Check One:

OIL WELL _____ GAS WELL _____ D & A _____ SWD or INJ WELL X DOCKET NO. D-21,019

SURFACE CASING SIZE 8 5/8" SET AT 257' CEMENTED WITH 200 SACKS

CASING SIZE 4 1/2" SET AT 4477' CEMENTED WITH 200 SACKS

PERFORATED AT 4130-4210 OA

CONDITION OF WELL: GOOD X POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL To KCC requirements

RECEIVED
STATE CORPORATION COMMISSION

(If additional space is needed use back of form) AUG 30 1989

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACCOMPANIED BY _____
(If not, explain) yes
Conservation Division
Wichita, Kansas

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN ASAP

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Sierra Drilling Co. PHONE # () _____

ADDRESS P.O. Box 782050 Wichita, Kansas 67278

* PLUGGING CONTRACTOR Kelso Casing Pulling, Inc. LICENSE NO. 6050 12/89

ADDRESS Box 347 Chase, KS. 67524 PHONE # (316) 938-2457

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Wesley Hansen - Agent
(Operator or Agent)

(2) DATE: August 16, 1989

TXO PRODUCTION CORP.
200 W. DOUGLAS, #300
WICHITA, KS 67202
CONTR FWA DRLG. CTY SUMNER

29-30-3W
#2 "A" FRIESS 1650' FSL &
1200' FWL, SW/4

GEOL WILLIAM CLARK FIELD CONWAY WEST

E 1368 KB CM 4/15/82 CARD ISSUED 7/1/82 IN SWDW

API 15-191-21,415

MISS 4130-4210 OA

LOG	TOPS	DEPTH	DATUM
IEEB		2679	-1311
STAL		2980	-1612
KC		3271	-1903
SWOPE		3410	-2042
CHER		3700	-2332
MISS		3876	-2508
KIND		4226	-2858
SIMP		4310	-2942
ARB		4416	-3048
RTD<D		4478	-3110

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

8-5/8" 257/200sx, 4 1/2" 4477/200sx

DST (1) 3406-27(KC,SWOPE)/30-60-45-
90, REC 31' SOCM, 124' DM, 124' MSW,
SIP 1221-1220#, FP 129-149/149-
189#

MIST - CO, PF (SIMP) 16/4310-15, REC
4 BW/45", FL AT 1200', SWB 6 BBLS FL
W/TR OIL, SQZ'D PFS AT 4310-15 W/100sx.
CO AT 4454', SWB DWN, PF 11/4310-15,
SWB DRY, AC 500G (15% NE), SWB DWN
18 BF W/SO, SWB 3.48 BPPH W/220,
SITP=1-#, SICP=0#, 2800' FIH W/RESO,
SET CIBP 4280', PF (MISS) 4190-4210
& 4130-50, W/1 SPF, FL AT 400', SWB
74.5 BBLS DIRTY FL, TOOK INJECTION
RATE W/46 BW AT 6 BPM & 350#, ISIP
0#, WELL ON VACUUM OF 2 BPM, SWD,
5/13/82

	+	+	+
	+	+	+
	+	+	+

D-21019

RECEIVED
STATE CORPORATION COMMISSION

AUG 3 1989

CONSERVATION DIVISION
Wichita, Kansas

RECEIVED
STATE CORPORATION COMMISSION

AUG 4 1989

CONSERVATION DIVISION
Wichita, Kansas

State of Kansas



MIKE HAYDEN
KEITH R. HENLEY
RICH KOWALEWSKI
MARGALEE WRIGHT
JUDITH McCONNELL
FRANK A. CARO, JR.

GOVERNOR
CHAIRMAN
COMMISSIONER
COMMISSIONER
EXECUTIVE DIRECTOR
GENERAL COUNSEL

Kansas Corporation Commission

THIS NOTICE

DEC 1 1989

EXPIRES

CONSERVATION DIVISION
SHARI FEIST ALBRECHT, DIRECTOR
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1286
(316) 263-3238

August 31, 1989
**NOTICE OF RECEIPT OF
WELL PLUGGING APPLICATION**

Plugger's, Inc.
P.O. Box 782050
Wichita, KS 67278

Friess SWD 2-A
29-30-03W
Sumner County

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office to review your proposed plugging method at least five (5) days before plugging the well.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. The CP-1 is simply reviewed to determine compliance with plugging rules and regulations.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

Shari Feist Albrecht
Shari Feist Albrecht
Director

District: #2 202 W. First, Suite 300
Wichita, KS 67202
(316) 263-8809