

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-095-21185-0000 (of this well) 6/87
(This must be listed; if no API# was issued, please note drilling completion date.)
(was Monsanto)

LEASE OPERATOR *BHP Petroleum Company, Inc. OPERATORS LICENSE NO. 5457

ADDRESS 3030 NW Expressway, Ste 1203, Okla. City, OK. 73112 PHONE # (405) 947-2361

LEASE (FARM) Ravenstein WELL NO. 1 WELL LOCATION NW NE NW COUNTY Kingman

SEC. 4 TWP. 30S RGE. 6 ~~(E)~~ or (W) TOTAL DEPTH 4420' PLUG BACK TO 4370'

Check One:

OIL WELL X GAS WELL _____ D & A _____ SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8 5/8" SET AT 237' CEMENTED WITH 250 SACKS

CASING SIZE 5 1/2" SET AT 4416' CEMENTED WITH 400 SACKS

Perf 4089-91' Set CIBP @ 4015'; Perf 3706-10' Set CIBP @ 3695';
PERFORATED AT 3670-72' Set CIBP @ 3650'; Perf 3560-67' 3526-32' Set CIBP @ 3460';
Perf 3244-48'.

CONDITION OF WELL: GOOD X POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Cap perforations w/50 sack cement plug, rip
5 1/2" casing @ cement top (2676'), spot 100' cement plug 50' above & below base surface casing,
plug surface casing from 40' to 5' below ground level & cut off surface & weld on ID plate.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN May 20, 1986

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Bill Allen PHONE # (316) 532-5238

ADDRESS 642 West "C" Street, Kingman, Kansas 67068

PLUGGING CONTRACTOR Pratt Well Service LICENSE NO. ~~5893~~ 5893

ADDRESS 107 West Fowler, Medicine Lodge, KS. 67104 PHONE # (316) 672-2531

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Paul H. [Signature]
(Operator or Agent)

*Formerly Monsanto Oil Company

DATE: April 30, 1986

RECEIVED
STATE CORPORATION COMMISSION
MAY 22 1986
CONSERVATION DIVISION
Wichita, Kansas

2

State of Kansas



JOHN CARLIN
MICHAEL LENNEN
MARGALEE WRIGHT
LEITH R. HENLEY
JUDITH A. McCONNELL
BRIAN J. MOLINE

Governor
Chairman
Commissioner
Commissioner
Executive Secretary
General Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
200 Colorado Derby Building
202 West 1st Street
WICHITA, KANSAS 67202-1286

THIS NOTICE

AUG 09 1986

EXPIRES

May 9, 1986

WELL PLUGGING NOTICE

Ravenstein #1
NW NE NW
Sec. 4-30S-6W
Kingman County

BHP Petroleum Company, Inc.
(Formerly Monsanto Oil Company)
3030 NW Expressway, Ste. 1203
Oklahoma City, OK 73112

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This notice is void after ninety (90) days from the above date.

Sincerely,

William R. Bryson, Director

Please contact the district office to review your suggested method of plugging
DIST. #2 3244 E. Douglas Wichita, KS 67208 316-651-5506
five days prior to plugging the well (KAR-82-3-113).