

Phoenix

15-175-20462-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Seward County. Sec. 36 Twp. 32S Rge. 32 ~~XX~~/~~XX~~W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines \_\_\_\_\_

C NE SW  
Lease Owner Phoenix Resources Co.  
Lease Name Massoni Well No. 1  
Office Address 3524 N.W. 56 Suite 300 Okla. City, Okla. 73112  
Character of Well (Completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Dry Hole

Date Well completed 4-13 1980  
Application for plugging filed 7-14 1980  
Application for plugging approved 7-16 1980  
Plugging commenced 7-22 1980  
Plugging completed 7-24 1980  
Reason for abandonment of well or producing formation \_\_\_\_\_  
Uneconomic

If a producing well is abandoned, date of last production \_\_\_\_\_  
19 \_\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Clarence Thomas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 6000  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Council Grove	Water	3036	3042	8 5/8	1495	none
Council Grove	Water	3160	3165	4 1/2	5734	2015
Cherokee	Oil/Gas/Water	5316	5322			
Morrow	Gas	5588	5596			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

- Set 35 sks. of cement from 5605 to 5145
- Spot 40 sks. of cement from 3400 to 2885
- Spot 35 sks. of cement from 1495 to 1395
- Spot 25 sks. of cement from 580 to 500
- Put 10 sks. of cement from 40 to 0

8-4-80  
STATE CORPORATION COMMISSION RECEIVED  
LATER  
CONSULTATION

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sargents Casing Pulling Service Box 506 Liberal, Kansas Ks. No. 511

STATE OF OKLAHOMA COUNTY OF OKLAHOMA, ss.  
Jim L. Harbolt for Phoenix Resources Co. (employee or owner) or (owner or operator)


of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jim L. Harbolt  
3524 NW 56th; Oklahoma City, OK 73112  
(Address)

SUBSCRIBED AND SWORN TO before me this 31st day of July, 19 80

Clarence Thomas  
Notary Public.

My commission expires ~~3-07-84~~ 3-07-84



DRILLERS LOG

MASSONI 1-36

CASING RECORD:  
8 5/8" set at 1495'  
w/900 sacks cement

OPERATOR: Phoenix Resources

DISCRIPTION:

CONTRACTOR: Search Drilling Co.

NE/4 SW/4,  
Section 36-32S-32W  
Seward County,  
Kansas

TOTAL DEPTH:  
6000'

COMMENCED: March 29, 1980

COMPLETED: April 13, 1980

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sand	63	590	
Red Bed & Sand	590	960	
Red Bed & Lime	960	1195	
Glorietta Sand	1195	1177	
Red Bed & Lime	1195	2086	
Lime and Shale	2086	3000	
Lime and Shale	3000	4164	
Lime and Shale	4164	5102	
Lime and Shale	5102	6000	
Rotary Total Depth	6000		

Ran 181 joints, 10 3/4",  
4 1/2" casing set at 5734'  
w/ 650 sacks 50-50  
posmix, 5% salt, 6#  
gilsonite. Plug down  
at 7:40 A.M. on April  
13, 1980.

I certify that this is a true and correct copy of the above log to the best of my knowledge.


SEARCH DRILLING COMPANY

*N.J. Johnson*  
\_\_\_\_\_  
N.J. Johnson

Subscribed and sworn to before me this 15th day of April, 1980.

My appointment expires:  
February 22, 1981

*Maxine Dressen*  
\_\_\_\_\_  
Maxine Dressen Notary Public



RECEIVED  
STATE CORPORATION COMMISSION

JUL 15 1980

CONSERVATION DIVISION  
Wichita, Kansas