

15-175-20225-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Seward County, Sec. 36 Twp. 32S Rge. (E) 32 (W)

Location as "NE/CNW/SW" or footage from lines C NE/4

Lease Owner Glen N. Rupe

Lease Name John Massoni Well No. 1

Office Address 925 Olive Garvey Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed May 10, 19 74

Application for plugging filed 19

Application for plugging approved 19


Plugging commenced May 10, 19 74

Plugging completed May 10, 19 74

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes, (Edgar Eves of Sublette)



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well

Producing formation Depth to top Bottom Total Depth of Well 5960 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	1420'	8-5/8"	1420'	None
	Casing					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy Mud from Total Depth to 1000 Feet,
35 sax Cement, Mud to 45 Feet, 15 sax
Cement 45' to 0'. Job Completed @ 2:15 A.M.

RECEIVED
STATE CORPORATION COMMISSION
5-16-74
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Dowell

Address 1229 N. Calhoun, Liberal, Ks. 67901

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
John R. Bartholomew of Sage Drilling Co. (employee of owner) or (owner or operator) of the above described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed and that the same are true and correct. So help me God.


(Signature) John R. Bartholomew

500 Biting Bldg., Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 15th day of May, 1974

My commission expires November 26, 1974.

Louise K. Whitted Notary Public.



DRILLERS LOG

JOHN MASSONI NO. 1

CASING RECORD:	OPERATOR: Glen N. Rupe	DESCRIPTION:
8-5/8" set @ 1420' w/600 sax cement	CONTRACTOR: Sage Drilling Co.	C NE/4 Sec. 36-32S-32W Seward County, Kansas
TOTAL DEPTH: 5960'	COMMENCED: April 23, 1974	ELEVATION: 2789KB
	COMPLETED: May 10, 1974	

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Sand & Red Bed	0	705	
Red Bed & Sand	705	1340	
Red Bed	1340	1420	
Anhydrite & Red Bed	1420	2175	
Shale & Lime	2175	2666	
Lime & Shale	2666	5571	
Shale & Lime	5571	5635	
Lime & Shale	5635	5955	
Lime	5955	5960	D&A

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 16 1974
 CONSERVATION DIVISION
 Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., INC.

By John R. Bartholomew



Subscribed and sworn to before me this 15th day of May, 1974.

Louise K. Whitted
Louise K. Whitted, Notary Public

My commission expires:
November 26, 1974.