

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-175-20257-0000

LEASE NAME Fedder, A

WELL NUMBER 1

3330 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 23 TWP. 32S RGE. 32 (E or W)

COUNTY Seward

Date Well Completed 8-6-75

Plugging Commenced 12-10-87

Plugging Completed 1-15-88

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Cities Service Oil and Gas Corporation

ADDRESS 3545 NW 58th Street, Oklahoma City, OK 73112

PHONE#(405) 949-4268 OPERATORS LICENSE NO. 5447

Character of Well gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? District #1

Is ACO-1 filed? yes If not, is well log attached? yes

Producing Formation Lansing A Depth to Top Sand Notch at 4344' Bottom T.O. 6142'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Lansing A	gas Sand	Notch	4344	8-5/8"	1719'	0
				5-1/2"	4450'	2638'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.
Pumped 2 sx hulls followed by 20 sx Cl H cmt. & top plug. Displaced cmt. & plug w/100 bbls. 9.0 ppg mud. Shot csg. at 3106' & 2840'; could not pull csg. Shot csg. at 2632' & pulled 240'. Pulled csg. to 1750'. Pumped 50 sx Cl H cmt. from 1750' to 1650'. Pulled csg. to 800'. Pumped 50 sx Cl H cmt. from 800'-700'. Set 10 sx cmt. plug from 40' to 4'. State Witness:

(If additional description is necessary, use BACK of this form.) Mr. G. Barlow

Name of Plugging Contractor Sargents Casing Pullers License No. RECEIVED

Address Liberal, KS STATE CORPORATION COMMISSION

STATE OF Oklahoma COUNTY OF Oklahoma, ss. JAN 28 1988

Del G. Oliver, Special Projects Manager (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Del G. Oliver

(Address) 3545 NW 58th Street Oklahoma City, Oklahoma 73112

SUBSCRIBED AND SWORN TO before me this 27th day of January, 19 88

Jessie Jo Howell
 Notary Public

My Commission Expires: 4-24-89