

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-62-3-117

API NUMBER 15-175-~~7057~~-0001 ⁰⁰²⁵⁷

LEASE NAME Fedder

WELL NUMBER A-1

3330 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 23 TWP. 32 RGE. 32 (E or W)

COUNTY Seward

Date Well Completed _____

Plugging Commenced 4-2-03

Plugging Completed 4-3-03

RECEIVED

MAY 02 2003

KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR First National Oil, Inc.

ADDRESS 150 Plaza Drive Suite B-3 Liberal KS 67901

PHONE (620) 624 1664 OPERATORS LICENSE NO. 6230

Character of Well GAS

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4-2-03 (date)

by Kevin Strube (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation Chase Depth to Top 2500 Bottom 2750 T.D. 2822

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	1719	-
CHASE	GAS / SALT WATER	2500	2750	5 1/2	2825	2312

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each as
Mixed 400 lb. hulls & 25 sx cmt. to plug perfs from 2630 to 2430. Cut & pull 5 1/2 to 1750. Circ. hole w/mud mixed 50 sx cmt 1750 to 1600 40 SX 550 to 430 10 SX 40 to 0 Cut off & capped 8 5/8 3 ft. below G.L.

Name of Plugging Contractor SARGENT AND HORTON PLUGGING, INC. License No. 31151

Address Route 1, Box 49BA Tyrone, OK 73951-9731 (580) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: First Nat'l oil

STATE OF Ks COUNTY OF Seward, ss.


Bill Carlisle

(Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) Bill Carlisle

(Address) Liberal, Ks.



SUBSCRIBED AND SWORN TO before me this 30 day of April, 2003

Sandra Carlisle
Notary Public

My Commission Expires: August 1, 2005