

020044

DEC 24 1986

To: 1  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-175-20,929-0000  
C NE, SEC. 12, T 32 S, R 32 W/E  
3960 feet from S section line  
1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4782  
Operator: Ensign Operating Company  
Name & Address 621 17th St., Suite 1140  
Denver, CO 80293

Lease Name Krause Well # 1-12  
County Seward 196.63  
Well Total Depth 6050 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 1644

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor H-30, Inc. License Number 5107

Address 251 N. Water, Suite 10, Wichita, KS 67202

Company to plug at: Hour: 1:30 a.m. Day: 24 Month: 12 Year: 19 86

Plugging proposal received from Ray

(company name) H-30, Inc. (phone) 316-263-2043

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2820'

1st plug at 3000-2700' with 100 sx cement, 2nd plug at 30' below base of surface pipe  
with 50 sx cement, 3rd plug at 750' with 25 sx cement, 4th plug at 40-0' with 10 sx  
cement, 5th plug to circulate rathole with 10 sx cement, 6th plug to circulate mousehole  
with 10 sx cement.

Plugging Proposal Received by Steve Durrant  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 10 a.m. Day: 24 Month: 12 Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 3000-2700' with 100 sx cement,  
2nd plug at 1670' with 50 sx cement,  
3rd plug at 750' with 25 sx cement,  
4th plug at 40-0' with 10 sx cement,  
5th plug to circulate rathole with 10 sx cement,  
6th plug to circulate mousehole with 10 sx cement.

STATE CORPORATION COMMISSION  
DEC 30 1986  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan.  
(if additional description is necessary, use BACK of this form.)

**INVOICED**

DATE 12-31-86

INV. NO. 15689  
12-24

Signed Glenn R. Barber  
(TECHNICIAN)

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date 12 6 86 month day year

API Number 15-175-20,929

OPERATOR: License # 4782 Name Ensign Operating Co. Address 621 17th St., Suite 1140 City/State/Zip Denver, CO, 80293 Contact Person Larry Hartnett Phone (303) 293-9999

C NE Sec. 12 Twp. 32 S, Rg. 32 East 3,960 Ft. from South Line of Section 1,320 Ft. from East Line of Section

CONTRACTOR: License # 5107 Name H-30, Inc. City/State Wichita, KS, 67202

(Note: Locate well on Section Plat on reverse side) Nearest lease or unit boundary line 1,320 feet County Seward

Well Drilled For: X Oil SWD Infield Mud Rotary X Gas Inj Pool Ext Air Rotary OWWO Expl Wildcat Cable

Lease Name Krause Well # 1-12 Ground surface elevation 2,815 feet MSL Domestic well within 330 feet: yes no

If OWWO: old well info as follows: Operator Well Name Comp Date Old Total Depth

Municipal well within one mile: yes no Depth to bottom of fresh water 493 Depth to bottom of usable water 710 500 Surface pipe by Alternate: 1 X 2

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications. Date 7 Nov, 26, 1986 Signature of Operator or Agent Mary S. Black Title Manager, Engineering

For KCC Use: Conductor Pipe Required 550 feet; Minimum Surface Pipe Required 550 feet per Alt. This Authorization Expires 6-1-87 Approved By 12-1-86

Spud 12-11-86 Set 8 7/8 @ 1644

Glenn Barlow plugged C NE Sec. 12 Twp. 32 S, Rg. 32 East West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

Table with columns for plug depth, feet depth, and sx/s of. Includes handwritten notes like 'BASE HUGANSD - TOP C.C.' and '3000' - 2700 - 80-10031'.

Form with fields for PUSHER, TD, SURFACE PIPE, ANHYDRITE, STARTING TIME & DATE, COMPLETION TIME & DATE, 1st PLUG @, 2nd PLUG @, 3rd PLUG @, 4th PLUG @, RAT HOLE CIRCULATED W/, MOUSE HOLE CIRCULATED W/, WATER WELL PLUGGED W/ Water Wells, CEMENT COMPANY, TECHNICIAN.

STATE CORPORATION COMMISSION DEC 30 1986 CONSERVATION DIVISION Wichita, Kansas