

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Dorby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-175-21041-0000

LEASE NAME Printz

WELL NUMBER 1-7

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div. NW  
office within 30 days.

NW 4620 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 7 TWP. 32S RGE. 32W (E) of (W)

LEASE OPERATOR Midwestern Exploration Co.

COUNTY Seward

ADDRESS PO BOX 1884 Liberal, Kansas 67905-1884

Date Well Completed 10-16-88

PHONE (316) 624-3534 OPERATORS LICENSE NO. 5263

Plugging Commenced 8-25-94

Character of Well Gas

Plugging Completed 8-30-94

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Lacy Dodge City

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing Formation HUGOTON Depth to Top 2664 Bottom 2730 T.D. 6042

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
HUGOTON	GAS	2664	2730			
				8 5/8	1605	0
				5 1/2	2862	2435

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set.

Pump 25 sks. of cement & 1 sk. of hulls to 2500'

Pump 50 sks. of cement from 1630' to 1530'

Pump 40 sks. of cement from 800' to 700'

Put 10 sks. of cement from 40' to 0' Cut off & cap 8 5/8" 3' below ground level

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547

Address P.O. Box 506 Liberal, Kansas 67905-0506

STATE OF Kansas COUNTY OF Seward, ss.

DALE J. LOLLAR, VICE-PRESIDENT (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed, that the same are true and correct, so help me God.

(Signature) Dale J. Lollar

(Address) PO BOX 1884, LIBERAL, KS. 67905-1884

SUBSCRIBED AND SWORN TO before me this 13<sup>th</sup> day of September, 1994

STATE NOTARY PUBLIC  
MARY MORGAN  
NOTARY PUBLIC  
STATE OF KANSAS  
My Appt. Expires: \_\_\_\_\_

Mary Morgan  
Notary Public

My Commission Expires: 8-3-96

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 14 1994  
WICHITA KANSAS