

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 COLORADO DERRY BUILDING
WICHITA, KANSAS 67202

WELL PLUGGING RECORD

API NUMBER 175-21050 -00-00

LEASE NAME Dorothy

WELL NUMBER 1-7

SPOT LOCATION SW-NE-NE

SEC. 7 TWP. 32 RGE. 32 (E) OR (W) (W)

COUNTY Seward

DATE WELL COMPLETED 11-22-88

PLUGGING COMMENCED 8-11-03

PLUGGING COMPLETED 8-13-03

AUG 28 2003

TYPE OR PRINT
PLEASE FILL OUT COMPLETELY
AND MAKE REQUIRED AFFIDAVIT.

KCC WICHITA

LEASE OPERATOR Midwestern Exploration Company

ADDRESS 3500 S. Boulevard/Suite 2B Edmond, Oklahoma 73013

PHONE # (405)-340-4300 OPERATORS LICENSE NO. 5263

CHARACTER OF WELL Oil
(OIL, GAS, D&A, SWD, INPUT, WATER SUPPLY WELL)

DID YOU NOTIFY THE KCC/KDHE JOINT DISTRICT OFFICE PRIOR TO PLUGGING THIS WELL? Yes

WHICH KCC/KDHE JOINT OFFICE DID YOU NOTIFY? Dodge City, Kansas

IS ACG-1 FILED? Yes IF NOT, IS WELL LOG ATTACHED? _____

PRODUCING FORMATION Herrington DEPTH TO TOP 2662 BOTTOM 2668 T.D. 2800

SHOW DEPTH AND THICKNESS OF ALL WATER, OIL AND GAS FORMATIONS.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Herrington	Gas Water Oil	2662	2668	20	30	-0-
				8 5/8	629	-0-
				4 1/2	2799	-0-

DESCRIBE IN DETAIL THE MANNER IN WHICH THE WELL WAS PLUGGED, INDICATING WHERE THE MUD FLUID WAS PLACED AND THE METHOD OR METHODS USED IN INTRODUCING IT INTO THE HOLE. IF CEMENT OR OTHER PLUGS WERE USED STATE, THE CHARACTER OF SAME AND DEPTH PLACED, FROM FEET TO FEET EACH SET. Set CIBP @1950'. Circulated 4 1/2" casing with mud leaving 25 sx. cement on top of CIBP. Pulled tubing up to 1700', circulated 4 1/2 casing full of cement with 165 sx. cement from 1700 to surface. Squeezed 10 sx. cement into 8 5/8 to 400 P.S.I. Cut off all strings 4' B.G.L. welded I.D. plate on top.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

NAME OF PLUGGING CONTRACTOR Jerry Dunkin, Inc. LICENSE NO. 8733

ADDRESS P.O. Box 389 Enid, Oklahoma 73702

STATE OF _____ COUNTY OF _____, SS.

Dale J. Lollar, President, Midwestern Exploration Co. (EMPLOYEE OF OPERATOR) OR (OPERATOR) OF ABOVE-DESCRIBED WELL, BEING FIRST DULY SWORN ON OATH, SAYS: THAT I HAVE KNOWLEDGE OF THE FACTS, STATEMENTS, AND MATTERS HEREIN CONTAINED AND THE LOG OF THE ABOVE-DESCRIBED WELL AS FILED THAT THE SAME ARE TRUE AND CORRECT, SO HELP ME GOD.

Midwestern Exploration Co.

(SIGNATURE) Dale J. Lollar

Dale J. Lollar, President


(ADDRESS) 3500 S. Boulevard, Ste. 2B

Edmond, Oklahoma 73013

SUBSCRIBED AND SWORN TO BEFORE ME THIS 28th DAY OF August, 2003

Virginia Means
NOTARY PUBLIC

MY COMMISSION EXPIRES: July 12, 2005



FORM CP-4
REVISED 06-83