

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

Seward County, Sec. 7 Twp. 32 Rge. 32W (E) (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines 100'N & 100'W of Center Section

Lease Owner American Gas Production Company

Lease Name Printz "A" Well No. 1

Office Address Bartlesville, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed October 1, 1951 19

Application for plugging filed October 1, 1951 19

Application for plugging approved October 3, 1951 19

Plugging commenced October 4, 1951 19

Plugging completed October 5, 1951 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production None 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well R. J. Phillippe

Producing formation Depth to top Bottom Total Depth of Well 2765 Feet

Show depth and thickness of all water, oil and gas formations. Ground Level

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	545	None
				5 1/2"	2764	None
Herrington	Salt Water	2670	2680			
U-Krider	" "	2696	2706			
L-Krider	" "	2724	2748			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy mud 2707 to 2665, 5' of 1" rock to 2660, 21' of cement to 2639',
Heavy mud to 34', 30' of cement to 4' below ground level; cut off casing
4' below ground level and welded on steel cap.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to H. V. Anderson

Address Box 70, Liberal, Kansas.

STATE OF Kansas, COUNTY OF Seward, ss.

American Gas Production Company (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) H. V. Anderson

Box 70, Liberal Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 18th day of October, 19 51

My commission expires 5-23-1953

J. T. Mabrey Notary Public.

PLUGGING CONSERVATION DIVISION
FILE SEC 7 T 32 R 32 W
BOOK PAGE 144 LINE 3
OCT 20 1951
Wichita, Kansas