

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-175-20452-0000 (of this well) 6/87
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Amoco Production Company OPERATORS LICENSE NO. 5952

ADDRESS P. O. Box 432 Liberal, KS 67901 PHONE # (316) 624-6241

LEASE (FARM) B. H. Lemert "B" WELL NO. 1 WELL LOCATION NE NE NE COUNTY Seward

SEC. 27 TWP. 32S RGE. 33 or (W) TOTAL DEPTH 6000 PLUG BACK TD 4686

Check One:

OIL WELL GAS WELL D & A SWD or INJ WELL DOCKET NO. _____

SURFACE CASING SIZE 8-5/8 SET AT 1586 CEMENTED WITH 650 SACKS

CASING SIZE 5-1/2 SET AT 6000 CEMENTED WITH 425 SACKS

PERFORATED AT 4782-87 4898-4900 5582-5600 5870-5883

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL See back of form

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN November 21, 1986

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Bob Heath PHONE # (316) 624-6241

ADDRESS P. O. Box 432 Liberal, KS 67901

PLUGGING CONTRACTOR To be bid LICENSE NO. 11-4-86

ADDRESS _____ PHONE # () _____

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Larry L. Smith
(Operator or Agent)

DATE: 11-3-86

①



Amoco Production Company
P. O. Box 432
Liberal, KS 67901

October 30, 1986

File: RAR-725-400.1

Plugging and Abandonment Procedure
B. H. Lemert "B" No. 1
Section 27-32S-33W
Seward County, Kansas

Detailed below is the recommended plugging and abandonment procedure for the subject well. Depths are relative to the Dual Induction log run by Schlumberger on April 11, 1980. Note that this procedure is for KCC permitting purposes only.

1. Locate free point of 5 1/2" casing (see attached wellbore sketch), cut off and pull casing. Estimated top of cement is 3950'.
2. Spot a 50 sack 50-50 Poz cement plug across the 5 1/2" casing stub.
3. Spot a 75 sack cement plug across the 8 5/8" surface casing shoe (50' in and out of casing shoe), shoe set at 1586'.
4. Spot a 50 sack cement plug from 40-5'.
5. Dig out cellar, cut off surface casing at 5'. Weld on steel cap with well and location I.D.
6. Restore location.

NOTE: All intervals between cement plugs must contain mud of at least 9.0 ppg density, and 36 quart-second API viscosity. A representative of the KCC must be notified at least five days prior to the actual plugging operation to discuss plugging methods. They (KCC) can be contacted at (316) 225-6760.

A wellbore sketch is attached for your reference.

C. H. Kelm

BSP/bka

Attachment

P&A/BSP

NOV 4 1986



JOHN CARLIN
MICHAEL LENNEN
MARGALEE WRIGHT
KEITH R. HENLEY
JUDITH A. McCONNELL
BRIAN J. MOLINE

Governor
Chairman
Commissioner
Commissioner
Executive Secretary
General Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
200 Colorado Derby Building
202 West 1st Street
WICHITA, KANSAS 67202-1286

Extension
THIS NOTICE
MAY 4 '87
EXPIRES
90-Days

THIS NOTICE
FEB 4 '87
EXPIRES

November 4, 1986

WELL PLUGGING NOTICE

B. H. Lemert "B" #1
NE NE NE
Sec. 27-32S-33W
Seward County

Amoco Production Company
P. O. Box 432
Liberal, KS 67901

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This notice is void after ninety (90) days from the above date.

Sincerely,

Jack McCord, Director

Please contact the district office to review your suggested method of plugging
DIST. #1 302 West McArtor Dodge City, KS 67801 316-225-6760
five days prior to plugging the well (KAR-82-3-113).