

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

Rev. 03/92

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-175-21428-0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Helmerich & Payne, Inc. RCC LICENSE # 5293
(owner/company name) (operator's)

ADDRESS P.O. Box 558 CITY Garden City

STATE Kansas ZIP CODE 67846 CONTACT PHONE # (316) 276-3693

LEASE Schmidt 7-2 WELL# B-2 SEC. 6 T. 31e R. 31 (East/West)

- NE -SW - NW SPOT LOCATION/QQQQ COUNTY Seward

3460 FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

3866 FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET#

CONDUCTOR CASING SIZE SET AT CEMENTED WITH SACKS

SURFACE CASING SIZE 8-5/8 SET AT 622 CEMENTED WITH 525 SACKS

PRODUCTION CASING SIZE 5 1/2 SET AT 2675 CEMENTED WITH 525 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: perforations 2648'-2660'

ELEVATION 2832/2842 T.D. 2676 PBD 2674 ANHYDRITE DEPTH 1790
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Pump 40 sacks 65/35 Poz "C" cement with bulls for perforation plug down casing. TTH w/ 2-3/8" tubing to approximately 750' pump 50 sxs 65/35 Poz "C" cement for plug from 750' to surface. Fill casing up with cement. Cut off casing 3' (If additional space is needed attach separate page) (over)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? yes

If not explain why?

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Ken Jehlik PHONE# (316) 276-3693

ADDRESS P.O. Box 558 City/State Garden City, Kansas

PLUGGING CONTRACTOR Halliburton RCC LICENSE #
(company name) (contractor's)

ADDRESS Liberal, Kansas PHONE # ()

PROPOSED DATE AND HOUR OF PLUGGING (If Known?)

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 1-13-95 AUTHORIZED OPERATOR/AGENT: Ken Jehlik
(signature)

below ground level, Weld on plate. Reclaim location.