

STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-129-30111-0000

LEASE NAME Clancy

MAR 13 1990

GRAHAM  
DALLAS

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER A

989' Ft. from S Section Line

1,662' Ft. from E Section Line

LEASE OPERATOR Graham Royalty, Ltd.

SEC. 27 TWP. 31S RGE. 42W (E) or (W)

ADDRESS P.O. Box 919 Liberal, Kansas 67905-0919

COUNTY Morton

PHONE (316) 626-7900 OPERATORS LICENSE NO. 03538

Date Well Completed 8-5-66

Character of Well Gas

Plugging Commenced 2-13-90

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 2-15-90

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Glenn Barlow

Is ACO-1 filed? Unknown If not, is well log attached? No

Producing Formation Morrow Depth to Top 4,870' Bottom 4,927' T.O. 5222

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Morrow	Gas	4,870	4,927	8 5/8	1425	0
				4 1/2	5056	1475

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from    feet to    feet each set.

Pump 20 sks. of cement from 4870 to 4670

Pump 40 sks. of cement from 1440 to 1320

Pump 35 sks. of cement from 700 to 600

Put 10 sks. of cement from 40 to 0 Cut off S cap 8 5/8 3' below ground level

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargents Casing Pulling Service License No. 6547

Address P.O. Box 506 Liberal, Kansas 67905-0506

STATE OF Kansas COUNTY OF Seward, ss.

Michael M. Ivy

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the top of the above-described well as filled that the same are true and correct,

RECEIVED  
MAR 3 1990  
(Signature) Michael M. Ivy

(Address) 29 LBJ Fwy, Dallas, TX 75240

MAR 16 1990  
CONSERVATION DIVISION  
Wichita, Kansas

SUBSCRIBED AND SWORN TO before me PRODUCTION 14th day of March, 1990

Marilyn F. Hulse  
Marilyn F. Hulse, Notary Public

Commission Expires: 10/28/92