


STATE OF KANSAS
STATE CORPORATION COMMISSION

15-129-00091-0000

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Morton County. Sec. 30 Twp. 31 Rge. (E) 12 (W)
Location as "NE/CNW/SW" or footage from lines C/NE 1/4
Lease Owner Durbin Bond & Co., Inc. & Lewis Drilling Company
Lease Name Reed Gas Unit Well No. 1
Office Address 915 Union Center, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 8-30-1957
Application for plugging filed 8-30-1957
Application for plugging approved 8-30-1957
Plugging commenced 8-30-1957
Plugging completed 8-30-1957
Reason for abandonment of well or producing formation _____



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. M. A. Rives
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	1195'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 650'.
Set bottom plug with 20 sacks cement.
Filled with mud to 35'. Set top plug
with 10 sacks cement. Filled to base
of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Lewis Drilling Company
Address 915 Union Center, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
J. Fred Hambright (employee of ~~owner~~ owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. Fred Hambright
915 Union Center, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of September, 1957
A. R. Derrington
(A. R. Derrington) Notary Public.

My commission expires August 20, 1960

RECEIVED
STATE CORPORATION COMMISSION

9-18-57 SEP 18 1957

CONF

PLUGGING
FILE SEC. 30 T. 31 R. 42W
BOOK PAGE 41 LINE 29

WELL LOG

15-129-00091-0000


COMPANY Durbin Bond & Lewis Drilling Company

SEC. 30 T. 31-S R. 42-W
LOC. C/NE 1/4

FARM Reed Gas Unit NO. 1

Morton

COUNTY KANSAS



TOTAL DEPTH 5123

COMM. 8-6-57

COMP. 8-30-57

SHOT OR TREATED

CONTRACTOR Lewis Drilling Company

ISSUED

CASING

20	10
15	8-5/8" - 1195'
12	6
13	5

ELEVATION 3518 K.B.

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

0 - 75	Sand & Shale
75 - 170	Sand
170 - 290	Red Rock & Shale
290 - 310	Sand & Red Beds
310 - 450	Sand
450 - 525	Sand & Red Beds
525 - 570	Sand & Shale
570 - 600	Anhydrite
600 - 1062	Red Beds & Lime
1062 - 1273	Sand
1273 - 1390	Red Bed & Sand
1390 - 1600	Red Beds
1600 - 2640	Shale & Lime
2640 - 2900	Shale
2900 - 4622	Lime & Shale
4622 - 4995	Shale
4995 - 5070	Shale & Sand
5070 - 5105	Lime & Sand
5105 - 5123	Lime, Chert, & Sand
5123 - T.D.	

GEOLOGIC TOPS

Wabaunsee	2715
Elmont	2980
Topeka	3134
LeCompton	3262
Hebner	3342
Toronto	3370
Lansing	3458
Cherokee	4066
Atoka	4304
Morrow	4950

PLUGGING
FILE SEC. 30 T. 31 R. 42W
BOOK PAGE 44 LINE 29

State of KANSAS }
County of SEDGWICK } SS:

I, J. Fred Hambright of the Lewis Drilling Company

upon oath state that the above and foregoing is a true and correct copy of the log of the Reed Gas Unit #1 well.

J. Fred Hambright
(J. Fred Hambright)

Subscribed and sworn to before me this 14th day of September 1957

RECEIVED
A. R. Derrington
NOTARY PUBLIC

My Commission Expires: August 20, 1960

SEP 18 1957 (A. R. Derrington)