

15-129-10-67-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Morton County, Sec. 12 Twp. 31S Rge. 42W (E) (W)

Location as "NE/CNW&SW" or footage from lines C SW/4

Lease Owner The Superior Oil Company

Lease Name Johns Unit Well No. 1

Office Address Box 690, Chickasha, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed February 4, 19 57

Application for plugging filed February 5, 19 57

Application for plugging approved February 6, 19 57

Plugging commenced May 6, 19 58

Plugging completed May 9, 19 58

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. M. A. Rives

Producing formation Depth to top Bottom Total Depth of Well 5297 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Morrow	Water	5150	5248	10-3/4"	1496'	None
					5297'	3242'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Placed 50 sack cement plug at 5174 ft. Hole filled with heavy mud.
 Pulled 3242 feet of 7" casing.
 Bailed mud to 600 ft. Pushed wooden plug to 600 ft.
 Dumped 25 sack cement plug on top of wooden plug.
 Filled 10-3/4" casing with gel to within 20 feet of surface.
 Placed wooden plug at 20 feet.
 Dumped five sacks cement on top of plug. Cement to surface.
 Welded steel cap on top of 10-3/4" casing.

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 13 1958
 CONSERVATION DIVISION
 Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Toland and Reeves

Address 1315 S. E. 29th St. Oklahoma City, Oklahoma

STATE OF Oklahoma COUNTY OF Grady ss.

O. V. Sivage, Petroleum Engr. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) O. V. Sivage

Box 690, Chickasha, Oklahoma (Address)

SUBSCRIBED AND SWORN TO before me this 12th day of May, 19 58

My commission expires Sept. 15, 1960

M. F. Fiegel Notary Public.

PLUGGING
 FILE SEC. T. R.
 BOOK PAGE LINE

15-129-10167-0000

THE SUPERIOR OIL COMPANY

Sec. 12-31-42 W

C SW/4

0- 244	Sand, shells and shale
244- 815	Red beds
815-1440	Shale and sand
1440-1508	Lime streaks and shale
1508-1923	Shale and sand
1923-2205	Shale and lime streaks
2205-2345	Shale and sand
2345-2467	Shale and lime streaks
2467-2481	Shale and shells
2481-2490	Shale and lime streaks
2490-2509	Shale and lime
2509-2592	Shale and sand
2592-2836	Shale and lime
2836-3025	Shale and lime w/sand streaks
3025-3571	Shale and lime
3571-3599	Sand
3599-3698	Shale and lime
3698-3721	Sand and shale
3721-3783	Shale and lime, sandy
3783-3883	Shale and lime w/streaks of sand
3883-3928	Shale and lime
3928-4026	Lime w/shale streaks
4026-4144	Shale and lime
4144-4236	Shale and lime w/sand streaks
4236-4288	Shale and lime
4288-4360	Lime w/shale streaks
4360-4416	Shale and lime
4416-4738	Lime
4738-4851	Lime and shale
4851-4980	Lime
4980-5103	Shale w/lime streaks
5103-5188	Shale and lime
5188-5215	Shale and sand w/lime streaks
5215-5278	Sand
5278-5280	Lime
5280-5297	Shale and lime
T.D.	

RECEIVED
 PLUGGING
 FILE SEC 12 T. 31 R. 42 W - 6 1957
 BOOK PAGE 139 LINE 4
 MINING DIVISION
 WICHITA, KANSAS