

15-129-10162-0000
WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Morton County, Sec. 14 Twp. 31S Rge. (E) 42 (W)

Location as "NE/CNW/SW" or footage from lines C NW/4

Lease Owner The Superior Oil Company

Lease Name Garner Unit Well No. 1

Office Address P.O. Box 200, Casper, Wyoming 82601

Character of Well (completed as Oil, Gas or Dry Hole) Gas

Date well completed September 12 19 57

Application for plugging filed March 17 19 70

Application for plugging approved March 20 19 70

Plugging commenced April 17 19 70

Plugging completed April 20 19 70

Reason for abandonment of well or producing formation Well depleted

If a producing well is abandoned, date of last production February 3 19 70

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well E. Eves

Producing formation Morrow Depth to top 5052 Bottom 5191 Total Depth of Well 5212 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Morrow	Gas	5052	5191	8-5/8"	1535'	0
				5-1/2"	5210'	2718'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Left plug (bull-plugged packer) at 5170 feet. Pumped 2 sacks hulls and 25 sacks cement down 5-1/2" casing and displaced with 100 bbls. fresh water. Plug from 4000 to 4200 feet. Shot and recovered 2718 feet 5-1/2-inch casing. Pulled casing to 1900 feet. Filled hole with mud-laden fluid. Spotted 35 sack cement plug from 800 to 900 feet. Finished pulling casing. Placed 15 sack cement plug in top of surface pipe from surface to 45 feet. Cut off casing 4 feet below ground level. Welded on plate.

RECEIVED
STATE CORPORATION COMMISSION
APR 27 1970
CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Sargent Casing Pullers
Address Box 506, Liberal, Kansas

STATE OF WYOMING, COUNTY OF NATRONA, ss.
Herman High (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Herman High
P. O. Box 200, Casper, Wyoming 82601
(Address)

SUBSCRIBED AND SWORN to before me this 23rd day of April, 1970

September 9, 1973
My commission expires
J. R. Voris Notary Public