

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-129-10165-0000

LEASE NAME Herron

WELL NUMBER # 1

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 4 ^{C-Nw} TWP. 31 RGE. 42 (E) or (W)

COUNTY Morton

Date Well Completed 9/27/55

Plugging Commenced 8/19/88

Plugging Completed 8/25/88

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Gas Marketing

ADDRESS Box 159
Stafford, KS 67578

PHONE # (316) 234-5191 OPERATORS LICENSE NO.

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? #6 Hays, KS

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 5335'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				10-3/4	800	none
				7	200	1887

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Plugged off bottom with sand to 3300' and 70 sacks cement, shot pipe @2810, 2400', 2215', 2000', 1887', pulled 19 jts., pumped 5 sx of gel; 70 cement, pulled 10 jts., pumped 10sx gel, pulled 10 jts, pumped 15 sx gel & 50 cement, pulled 20 jts., pumped 15 sx cement. plugged w/35sx 60/40pos 3%, 30 gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address P.O. Box 347 Chase, KS 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, KS 67524

RECEIVED
 STATE CORPORATION COMMISSION

SUBSCRIBED AND SWORN TO before me this 29th day of August, 1988
AUG 31 1988

Jane Hoover
 Notary Public

CONSERVATION DIVISION
 Commission Expires:
 Wichita, Kansas

