

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

15-175-00425-0000

API NUMBER Completed 10-27-55

LEASE NAME Schmidt

WELL NUMBER B-1

3847 Ft. from S Section Line

3686.4 Ft. from E Section Line

SEC. 6 TWP. 31s RGE. 31 (E) or (W)

COUNTY Seward

Date Well Completed 10-27-55

Plugging Commenced 11-16-94

Plugging Completed 11-16-94

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Helmerich & Payne, Inc.

ADDRESS P.O. Box 558 Garden City, KS 67846

PHONE# (316) 276-3693 OPERATORS LICENSE NO. 5293

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8-3-94 (date)

by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached?

Producing Formation Hugoton Chase Depth to Top 2642 Bottom 2652 T.D. 2747

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Hugoton Chase	Gas	2642	2652	8-5/8	578	0
				5 1/2	2747	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each section. A 150 sks cement plug was pumped down casing from the perforations at 2642'-2644' to a depth of 697'. A 20 sk plug was placed from 650' to 350'. A 5 sk cement plug was placed from 40' to surface. 70 sacks were pumped between the 8-5/8"x5 1/2" annulus. All cement plugs consisted of 65/35 Poz "C" cement w/ 6% gel mixed at 12.3 PPG with a yield of 2.06 ft³/sk. (If additional description is necessary, use BACK of this form.) (over)

Name of Plugging Contractor Halliburton License No. 17661 & 2100

Address _____

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Helmerich & Payne, Inc.

STATE OF Kansas COUNTY OF Finney, ss.

KEN JEHLIK (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated, and matters herein contained and the log of the above-described well as filed and the same are true and correct, so help me God.

(Signature) [Signature]

(Address) Box 558 Garden City, KS

SUBSCRIBED AND SWORN TO before me this 21st day of November, 19 94

My Commission Expires: August 15, 1996

Glen Barlow of KCC's Dodge City office witnessed plugging.

