

15-175-20643-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Seward SEC. 14 TWP. 31S RGE. 31 ~~E~~W  
Location as in quarters or footage from lines:  
2000' FNL & 330' FEL of Section (SE SE NE)


Lease Owner ARCO Oil and Gas Company  
A Division of Atlantic Richfield Company  
 Lease Name Ruby Dee Well No. 1  
 Office Address P. O. Box 521, Tulsa, Oklahoma 74102  
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole  
 Date Well Completed Reached TD 7-13-82  
 Application for plugging filed Verbal approval \*  
 Plugging commenced 7-14-82  
 Plugging completed 7-15-82  
 Reason for abandonment of well or producing formation Dry Hole

Locate Well  
correctly on above  
Section Platt.

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt \*

Producing formation Dry Depth to top \_\_\_\_\_ bottom T.D. 6100'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
<u>Heebner</u>	<u>Shale</u>	<u>4229'</u>		<u>8-5/8"</u>	<u>1522'</u>	<u>None</u>
<u>Lansing-Kansas City</u>	<u>Water</u>	<u>4335</u>				
<u>Cherokee</u>	<u>No Porosity</u>	<u>5088</u>				
<u>Morrow</u>	<u>" "</u>	<u>5415</u>				
<u>Mississippian</u>	<u>Water</u>	<u>5464</u>				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Circulate & condition hole w/8.9# mud. Rig up B-J Hughes & pump 50 sks 50-50 poz 2850' to 2647'. Pumped 50 sks 50-50 poz 1550' to 1359'. Pumped 50 sks 50-50 poz 420' to 229'. Spotted 10 sks 50-50 poz 40' to 4'. Cut off 8-5/8" surface casing 4' below surface.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor B-J Hughes, Inc.

STATE OF Oklahoma COUNTY OF Tulsa, ss.

G. L. Weger (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) G. L. Weger  
G. L. Weger; Dist Drlg Supt, Box 521, Tulsa, Ok  
(Address) 74102

SUBSCRIBED AND SWORN TO before me this 19th day of July, 19 82

My Commission expires: July 22, 1986

Marion Mallory  
Notary Public  
STATE CORPORATION COMMISSION

RECEIVED  
STATE CORPORATION COMMISSION

JUL 26 1982

CONSERVATION DIVISION  
Wichita, Kansas