

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 175-21790-0000

LEASE NAME Unruh A

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

460 Ft. from (S) Section Line

330 Ft. from (W) Section Line

SEC. 24 TWP. 31 RGE. 31 (E) or (W)

COUNTY Seward

LEASE OPERATOR Daystar Petroleum, Inc.

ADDRESS 1321 W 93rd Street North

PHONE# (316) 755-3523 OPERATORS LICENSE NO. 30931

Character of Well _____

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Well Completed 3-18-00

Plugging Commenced 3-18-00

Plugging Completed 3-18-00

~~The plugging proposal was approved on MARCH 18, 2000 (date)~~

~~by RICHARD LACEY, DODGE CITY (KCC District Agent's Name)~~

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 6070

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Swope	G. O. W		1727	8 5/8	1727	0
Marmaton	G. O					
Morrow/Chester	G					
St. Louis	G. O					

~~Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet, each section.~~

Name of Plugging Contractor Murfin Drilling Co., Inc. License No. 30306

Address 250 N. Water, Ste. 300, Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Daystar Petroleum, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Charles Schmidt

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the same are true and correct to the best of my knowledge and belief, help me God.

(Signature) Charles Schmidt


(Address) 1321 W. 93rd St. North, Valley Center, KS

NOV 2 2000

SUBSCRIBED AND SWORN TO before me this 6 day of September 16 2000
Wichita, Kansas

Marsha Breitenstein
Notary Public

My Commission Expires: 9-15-2003



Form CP-4
Revised 05-88



CEMENTING LOG

WICHITA
STAGE NO.

Date 3-18-00 District Med-Lodge Ticket No. 1087
 Company Daystar Petroleum Rig Murf. 22nd
 Lease UNRHT Well No. A-1
 County Seward State KS.
 Location PLAINS + 160 Field 24-31s-31w
Sec. 4 N 3/4

CASING DATA: PTA Squeeze
 Surface Intermediate Production Liner
 Size _____ Type _____ Weight _____ Collar _____

Casing Depths: Top _____ Bottom _____

Drill Pipe: Size 4 1/2 Weight 16.60 Collars _____
 Open Hole: Size 7 7/8 T.D. _____ ft. P.B. to _____ ft.

CAPACITY FACTORS:
 Casing: Bbls/Lin. ft. 0.137 Lin. ft./Bbl. 15.20
 Open Holes: Bbls/Lin. ft. 0.102 Lin. ft./Bbl. 16.59
 Drill Pipe: Bbls/Lin. ft. 0.142 Lin. ft./Bbl. 20.32
 Annulus: Bbls/Lin. ft. 0.406 Lin. ft./Bbl. 24.64
 Bbls/Lin. ft. 0.440 Lin. ft./Bbl. 22.72

Perforations: From _____ ft. to _____ ft. Amt. _____

CEMENT DATA:
 Spacer Type: Freshwater
 Amt. _____ Skys Yield _____ ft³/sk Density _____ PPG

LEAD: Pump Time _____ hrs. Type 60:40:6 1/4 ft. 9"
 Excess _____

Amt. 125 Skys Yield 1.57 ft³/sk Density 13.8 PPG
 TAIL: Pump Time _____ hrs. Type _____

Amt. _____ Skys Yield _____ ft³/sk Density _____ PPG
 WATER: Lead 2.8 gals/sk Tail _____ gals/sk Total 24 Bbls.

Pump Trucks Used: 343 Mark B
 Bulk Equip. 240-250 David W.

Float Equip: Manufacturer _____
 Shoe: Type _____ Depth _____
 Float: Type _____ Depth _____
 Centralizers: Quantity _____ Plugs Top _____ Btm. _____
 Stage Collars _____
 Special Equip. _____
 Disp. Fluid Type Fresh Mud Amt. _____ Bbls. Weight _____ PPG
 Mud Type _____ Weight _____ PPG

COMPANY REPRESENTATIVE Tom Heskett CEMENTER Carl Bolding

TIME	PRESSURES PSI		FLUID PUMPED DATA			REMARKS
	DRILL PIPE CASING	ANNULUS	TOTAL FLUID	Pumped Per Time Period	RATE Bbls Min.	
11:55	200		8.5	8.5	5 1/2	1st plug 1750' - 50 sx
	250		22.5	14	5 1/2	start Freshwater
	100		25.25	2.75	3	dump 50 sx cement
	50		41.25	7.6	5	start Freshwater
						start Mud-Displacement
12:45 pm	150		49.75	8.5	5 1/2	2nd plug 600' - 40 sx
	150		61	11.25	5 1/2	start Freshwater
	50		63.75	2.75	5	dump 40 sx cement
	50		66.75	3	4	start Freshwater
						start Mud-Displacement
1:00			69.75	3	2 1/2	3rd plug 40' - 10 sx
			72.75	3	2	mouse hole - 10 sx
			77	4.25	2	rat hole - 15 sx

RECEIVED
 STATE CORPORATION COMMISSION

NOV 2 2000

ALLIED CEMENTING CO., INC.

Well File
1087

Federal Tax I.D.# 48-0727860

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT
Medicine hedge

DATE <u>3-18-00</u>	SEC. <u>24</u>	TWP. <u>31S</u>	RANGE <u>31W</u>	CALLED OUT <u>6:30 AM</u>	ON LOCATION <u>11:00 AM</u>	JOB START <u>11:55 AM</u>	JOB FINISH <u>1:45 pm</u>
LEASE <u>ONRUH</u>		WELL# <u>A-1</u>	LOCATION <u>Plains + 160th</u>		COUNTY <u>Seward</u>	STATE <u>Ks.</u>	
OLD OR NEW (Circle one)							

CONTRACTOR Muefin #22

TYPE OF JOB Rotary plug

HOLE SIZE 7 7/8 T.D.

CASING SIZE 8 5/8 DEPTH 1727

TUBING SIZE DEPTH

DRILL PIPE 4 1/2 DEPTH 1750

TOOL DEPTH

PRES. MAX 250 MINIMUM

MEAS. LINE SHOE JOINT

CEMENT LEFT IN CSG.

PERFS.

DISPLACEMENT

OWNER Daystar Petroleum

CEMENT AMOUNT ORDERED
125 5x 60' 40' 6+ 1/4 Flo-seal

COMMON @

POZMIX @

GEL @

CHLORIDE @

HANDLING @

MILEAGE @

TOTAL @

EQUIPMENT

PUMP TRUCK # 343 CEMENTER Carl Bolding

BULK TRUCK # 240-250 DRIVER David W.

BULK TRUCK # DRIVER

REMARKS:

pump 50 5x 1750

40 5x 600

10 5x 40

10 5x mouse hole

15 5x RAT Hole

SERVICE

DEPTH OF JOB 1750

PUMP TRUCK CHARGE

EXTRA FOOTAGE @

MILEAGE @

PLUG @

TOTAL @

CHARGE TO: Daystar Petroleum

STREET

CITY STATE ZIP

FLOAT EQUIPMENT

TOTAL

TAX

TOTAL CHARGE

DISCOUNT IF PAID IN 30 DAYS

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE [Signature]

PRINTED NAME TOM HESKETT

661