

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 007-220,26-000

LEASE NAME Bloom Jacobs

WELL NUMBER 1

SPOT LOCATION NW SE NW

SEC. 30 TWP. 32 SRGE. 12 (XXXX(W))

COUNTY Barber

Date Well Completed 4/27/85

Plugging Commenced 8/7/85

Plugging Completed 8/21/85

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Graves Drilling Co.

ADDRESS 910 Union Center, Wichita, KS 67202

PHONE # (316) 265-7233 OPERATORS LICENSE NO. 5428

Character of Well oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing formation Mississippi Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 4600

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	266	None
				4 1/2	4598	3469

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set. Sand from 4383 to 4475, 4sx cement with dump bailor from 4475 to 4440, 2sx hulls, 15sx jell, 50sx cement, 10sx jell, 1sx hull, plug, 125sx cement; 60-40 POZ, 6% jell

Sun pumping  
Shut in 600 - max 750

Jack Luthie and Elmo Morgenstern on location

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Clarke Corp. License No. 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

STATE OF Kansas COUNTY OF Barber, ss.

Elmo Morgenstern (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Elmo Morgenstern

(Address) Medicine Lodge, KS 67104

**CAREN J. McCULLOUGH**  
NOTARY PUBLIC  
STATE OF KANSAS  
My Appt. Exp. 6-29-87

SUBSCRIBED AND SWORN TO before me this 25 day of September, 1985

RECEIVED McCullough  
STATE CORPORATION COMMISSION PUBLIC

My Commission expires: June 29, 1987

SEP 27 1985

CONSERVATION DIVISION  
Wichita, Kansas

Form CP-4  
Revised 01-84