

OCT 13 1982 15-025-20796-00-01

WELL PLUGGING RECORD

CONSERVATION DIVISION  
Wichita, Kansas

Give All Information Completely  
Make Required Affidavit

COUNTY Clark SEC. 3 TWP. 31 RGE. 22W E/W  
Location as in quarters or footage from lines:  
860' SL 2080' EL SE


Locate Well  
correctly on above  
Section Platt.

Lease Owner Texas Energies, Inc.  
Lease Name Heilind 1-3 Well No. \_\_\_\_\_  
Office Address Box 947 Pratt, Kansas 67124  
Character of Well (Completed as Oil, Gas or Dry Hole): \_\_\_\_\_  
Date Well Completed \_\_\_\_\_  
Application for plugging filed \_\_\_\_\_  
Plugging commenced 10-6-82  
Plugging completed 10-8-82  
Reason for abandonment of well or producing formation \_\_\_\_\_

Depleted  
Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Paul Luthi  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 4864'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	261'	none
				4-1/2"	4743'	3436'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Pumped bottom with 60 sacks 50/50 pos, 3% gel, 3% cc and displaced plug to 4150' with 67 barrel of fresh water. Shot casing @3560' and 3480', pulled a total of 83 joints of 4-1/2" casing. Plugged well with 4 sacks hulls, 10 sacks gel, 50 sacks cement, 15 sacks gel, 1 sack hulls, and 100 sacks cement, 50/50 pos, 4% gel, 3% cc.

Plugging Complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso  
Box 347 Chase, Kansas 67524  
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of October, 19 82

My Commission expires: \_\_\_\_\_



Irene Hoover  
Notary Public.