


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Clark County, Sec. 5 Twp. 31S Rge. (E) 22 (W)
C SE/4 SE/4



Locate well correctly on above Section Plat

Location as "NE/CNW/SW" or footage from lines
Lease Owner Barbara Oil Company
Lease Name Young Bros Ranch No. 1 Well No. 1
Office Address 322 Central Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed June 14 19 61
Application for plugging filed June 14 19 61
Application for plugging approved June 14 19 61
Plugging commenced June 14 19 61
Plugging completed June 14 19 61
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Lackamp, Rt. #1, Stafford, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5423 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				13 3/8"	200'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy mud to 190'. Set Plug. Cemented with 30 sacks cement. Heavy mud to 35' Set Plug. Cemented with 15 sacks cement to bottom of cellar. Plugged rat hole with 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
JUN 23 1961
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Pickrell Drilling Company
Address 705 Fourth National Bank Bldg., Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
R. F. Ramsey (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. F. Ramsey
322 Central Building, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of June, 19 61

My commission expires March 2, 1965
Mildred Fisher Notary Public.

INVOICED
DATE 6/19/62
INV. NO. 5203-W

NOTARY DRILLING LOG

COMPANY: Barbara Oil Company
 322 Central Bldg.
 Wichita, Kansas

LOCATION: YOUNG BROS. RANCH No. 1 - C SE/4 SE/4,
 Sec. 5-31S-22W, Clark County, Kansas

Rotary Drilling Commenced 5/24/61

Rotary Drilling Completed 6/14/61

15-025-00056-1000

CONTRACTOR: **PICKRELL DRILLING COMPANY**
 Wichita, Kansas

CASING RECORD: 200' (5 jts.) 13 3/8" 48# Spiralweld Casing with 175 sacks cement.
 Circulated. No Oil String run. D & A

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

	<u>Circulated for Samples</u>	
200' Shale & Clay	4600'	
625' Red Rock, Gyp Rock & Shale	4709'	
1000' Red Rock & Shale	4795'	
1010' Red Rock	4850'	
1515' Shale & Red Rock	5000'	
1695' Anhydrite & Red Beds	5130'	
2275' Shale (red & blue) & Shells	5185'	
2678' Lime & Shale	5233'	
2760' Lime	5292'	
3300' Lime & Shale	5328'	
3328' Lime	5350'	
3458' Lime & Shale	5423'	
3555' Lime		
3955' Lime & Shale		
4205' Lime	<u>Slope Test</u>	
4452' Lime & Shale	500'	0°
4725' Lime	2000'	0°
4781' Lime & Chert	2500'	0°
4850' Lime	3000'	0°
4876' Lime & Shale	3500'	0°
5130' Lime	4000'	0°
5205' Lime & Shale	4500'	0°
5233' Lime & Chert	5000'	0°
5303' Cherty Lime & Shale		
5343' Lime & Chert	<u>S. L. M.</u>	
5361' Mississippi	1695'	
5391' Lime & Chert	2996'	
5423' Mississippi T.D.	4500'	
	5361'	

RECEIVED
 STATE CORPORATION COMMISSION

JUN 23 1962

CONSERVATION DIVISION
 Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By C. W. Sebitts Attorney-in-Fact

STATE OF KANSAS }
 COUNTY OF SEDGWICK } ss.

On this 21st day of June, 1961, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. Sebitts to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: September 24, 1962

Maxine Johnson
 Notary Public
 Maxine Johnson