

15-025-20734-0000

WELL PLUGGING RECORD

Give All Information Completely  
 Make Required Affidavit

COUNTY Clark SEC. 17 TWP. 31 RGE. 22 SW  
 Location as in quarters or footage from lines:  
2640 FSL 861 FEL


Locate Well  
 correctly on above  
 Section Platt.

Lease Owner T.D.R. Exploration Company  
 Lease Name Young Brothers Cattle Company Well No. #1A-17  
 Office Address 3816 N. Meridian Suite 113, Okla. City, Okla. 73112  
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole  
 Date Well Completed \_\_\_\_\_  
 Application for plugging filed \_\_\_\_\_  
 Plugging commenced 10-20-83  
 Plugging completed 10-21-83  
 Reason for abandonment of well or producing formation  
Dry Hole

Was permission obtained from the Conservation Division or it's  
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bob Tarbutton  
 Producing formation None Depth to top \_\_\_\_\_ bottom T.D. 5268

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
					None	

Describe in detail the manner in which the well was plugged, indicating where the mud  
 fluid was placed and the method or methods used in introducing it into the hold. If cement  
 or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
 to \_\_\_\_\_ feet for each plug set. Lay 60 sk cement plug @ 1200'

Lay 50 sk cement plug @ 720'  
Lay 10 sk cement plug @ 41'  
Lay 15 sk cement plug in Rathole  
 Cement is 60/40 Poz with 2% Gel, 3% C.C.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Buie Company, Inc. #2204

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

R.C. Floyd (employee of owner) or (owner or operator) of the  
 above-described well, being first duly sworn on oath, says: That I have knowledge of the  
 facts, statements, and matters herein contained and the log of the above-described well as  
 filed and that the same are true and correct. So help me God.

(Signature) R.C. Floyd  
3816 N. Meridian # 113, Okla. City, Ok  
 (Address) 73112

SUBSCRIBED AND SWORN TO before me this 26 th day of October, 19 83

My Commission expires: My Commission Expires Sept. 3, 1985

Mary Lou Bailey  
 Notary Public.

RECEIVED  
 STATE CORPORATION COMMISSION  
 NOV 8 1983  
 CONSERVATION

GABBERT-JONES, INC.  
WICHITA, KAS.

DRILLERS WELL LOG

15-025-25734-0000

YOUNG BROS. CATTLE CO. "A" - 1  
750' W of E/2 Sec. 17-31S-22W  
Clark County, Kansas

COMMENCED: 10/10/83  
COMPLETED: 10/21/83


OPERATOR: T-D-R EXPLORATION CO.

DEPTH		FORMATION	REMARKS
From	To		
0	375	Sand-Redbed-Shale	
375	2129	Shale	Ran 15 jts. of 24# 8 5/8"
2129	2168	Anhydrite	set @ 650' cemented w/300 sx.
2168	4100	Shale-Lime	11# - 100 sx. class H - 3% CC -
4100	5030	Lime-Shale	1/2# per sack seflake. P.D. 2:30
5030	5210	Lime	PM - 10/11/83
5210	5268	Lime-Shale	
5268		T.D.	D & A

State of Kansas ]  
County of Sedgwick ]

I, the undersigned, being duly sworn on oath,  
state the above Drillers Well Log is true and correct  
to the best of my knowledge and belief and according  
to the records of this office.

GABBERT-JONES, INC.

  
JAMES S. SUTTON, II - President

Subscribed & Sworn to before me  
this 24th day of October, 1983.

  
Lola Lenore Costa

My Commission expires November 21, 1984.

