

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-119-20-551-00-00

LEASE NAME Ediger

WELL NUMBER 1-36

SPOT LOCATION C SW SW NE

SEC. 36 TWP. 33 RGE. 27(E) or (W)

COUNTY Meade

Date Well Completed 3-10-83

Plugging Commenced 11-9-84

Plugging Completed 11-14-84

RECEIVED

NOV 21 '84

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Irex Corp. Protection Department

ADDRESS P.O. Box 508 Protection, KS 67127

PHONE # (316) 622-4582 OPERATORS LICENSE NO. 5760

Character of Well Gas
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Kansas

Is ACO-1 filed? yes/6-27-83 If not, is well log attached? _____

Producing formation Chester Depth to top 5890' bottom 6224' T.D. 6489'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Heebner	Shale	4550'				
Lansing		4652'		4 1/2"	6100'	3018.06'
Cherokee	Shale	5550'		8 5/8"	1448'	None
Morrow	Shale	5800'				
Chester		5885'				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Set a CIBP @ 5840' + 4 sacks cement on top. Pipe was shot and started @ 3007' and pulled up to 1490'. Pumped 50 sacks cement from 1490-1390' Pulled up to 750'. Pumped 40 sacks cement from 750-650'. Finished pulling pipe out of hole. Capped surface with 10 sacks cement from 3-33' and welded on a steel plate.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Reeves & Wilson, Inc. License No. 6083
Address P.O. Box 963 Woodward, Oklahoma 73802

RECEIVED
STATE CORPORATION COMMISSION

STATE OF Colorado COUNTY OF Denver, ss. JAN 24 1985

William H. Bauliff Operations Mgr. of TREC Corp. (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) William H. Bauliff

(Address) 1331-17th Street, Suite 800

Denver, CO 80202

SUBSCRIBED AND SWORN TO before me this 17th day of January, 1985

Kerry J. Harrell
Notary Public

Kerry J. Harrell, Notary Public

1331 17th Street, Suite 800

Denver, Colorado 80202 Form CP-4
Revised 01-84

My Commission expires: My Commission expires March 28, 1988